STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

			NON-GOVMNT PART.	EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						22	22	m3	COMMON EXCAVATION	203.15	1
						80	80	m3	EXCAVATION OF SURFACES AND PAVEMENTS	203.28	3
						10	10	m3	EARTH BORROW	203.30	EST.
						1950	1950	m	SHOULDER BERM REMOVAL	203.99	29
						10	10	m3	TRENCH EXCAVATION OF EARTH	204.20	EST.
						19180	19180	m2	COLD PLANING BITUMINOUS PAVEMENT	210.10	194
						4.5	4.5	m2	SCARIFYING PAVEMENT	212.10	0
						3440	3440	t	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	EST
						810	810	t	AGGREGATE SHOULDERS	402.12	EST.
						2200	2200	t	AGGREGATE SHOULDERS(MOD.)	402.12	EST.
						16400	16400	kg	EMULSIFIED ASPHALT	404.65	182
						17600	17600	t	BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.25	72
						1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (NOT A BID ITEM)	406.50	-
					1		1	m3	CONCRETE, CLASS A	501.22	EST.
					100		100	kg	REINFORCING STEEL	507.15	EST.
					18		18	m	BRIDGE EXPANSION JOINT	516.10	0.6
					78		78		REMOVAL OF EXISTING RAILING	525.10	
					78		78		BRIDGE RAILING--HD STEEL BEAM/CURB MOUNTED(MOD. 2)	525.40	
						30	30	m	300 mm CSP 1.63 mm (68 mm X 12 mm)	601.0005	0
						7	7	EA	CHANGING ELEV. OF DROP INLETS, CATCH BASINS OR MANHOLES	604.40	EST.
						1	1	EA	REHABING DICB OR MH CLASS I	604.412	EST.
			7				7	EA	CHANGING ELEVATION OF SEWER MANHOLE	604.42	EST.
						215	215	HR	POWER GRADER RENTAL	608.15	EST.
						215	215	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
						125	125	HR	POWER BROOM RENTAL	608.30	EST.
						35	35	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
						215	215	HR	TRUCK RENTAL	608.37	EST.
						215	215	HR	LOADER RENTAL, TYPE I	608.40	EST.
						10	10	m3	STONE FILL, TYPE I	613.10	EST.
						6	6	m	GRANITE SLOPE EDGING	616.20	0
						22	22	m	VERTICAL GRANITE CURBING	616.21	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING BIT. PAVEMENT
		VT ROUTE 131, CAVENDISH
300	m2	BEGINING OF PROJECT
10874	m2	FROM STA 0+258 TO 1+474
7241	m2	FROM STA 2+889 TO 3+769
374	m2	APPROACHES TO BRIDGE #4
		VT ROUTE 131, WEATHERSFIELD
197	m2	END OF PROJECT
18986	m2	SUBTOTAL
194	m2	ROUNDING
19180	m2	TOTAL
		AGGREGATE SHOULDERS
2290	t	VT ROUTE 131, CAVENDISH
75	t	GUARDRAIL TERMINALS
177	t	TREATED TIMBER CURBING
439	t	VT ROUTE 131, WEATHERSFIELD
2981	t	SUBTOTAL
29	t	ROUNDING
3010	t	TOTAL
		BITUMINOUS
		CONCRETE PAVEMENT (PG 58-28)
11121	t	VT ROUTE 131, WEARING COURSE (TYPE III)
4170	t	VT ROUTE 131, LEVELING COURSE
187	t	SIDE ROADS
50	t	DRIVES
2000	t	ADDITIONAL LEVELING
17528	t	SUBTOTAL
72	t	ROUNDING
17600	t	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

FINAL QUANTITIES ARE ARCHIVED WITH THE FIELD BOOKS

ARCHIVED IN DPR

PROJECT : CAVENDISH - WEATHERSFIELD	PROJECT NO. : STP 9661(I)S
DESIGN FILE NAME: /pave/95cl34/pcl34.dgn	
IPARM FILE NAME: pcl34qsl.i	PLOT DATE: 27-JAN-2006 14
SURVEYED BY: CLD Inc.	SURVEY DATE: 06/97
SQUAD LEADER: JAW	DRAWN BY: JPC
	SHEET: 4 OF 32