STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.9	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
												OPTION ITEMS																								
CAVENDISH																																		
STA 0+012 LT	STOP 1310 1406 0001	1	750	750	0.56		1				1			X			X																E-143M
STA 0+060 LT	ONLY ONLY	1	900	750	0.68						1			X			X																E-145AM
STA 0+258 LT		1	900	900	0.81						1			X			X																E-150M
STA 0+665 RT	SCHOOL	1	600	200	0.12						1			X			X																E-153M
	SPEED LIMIT 25	1	600	750	0.45																												E-142M
	WHEN CHILDREN ARE PRESENT	1	600	250	0.15																												E-153M
STA 0+730 RT		1	750	750	0.56						1			X			X																E-153M
STA 0+737 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X			X																E-141M
STA 0+747 RT	STOP 1310 1406 0046	1 1	750 150	750 200	0.56 0.03						1			X			X														BACK TO BACK		E-143M E-138M
STA 0+777 RT		1	300	300	0.09						1			X			X																E-143M
	END	1	600	300	0.18																												E-140M
STA 0+875 RT		1	750	750	0.56						1			X			X																E-153M
	TO	1	600	750	0.45																												E-146M
												m	m	41.4	m	m	41.4		EA	kg	kg	kg		kg	kg	kg	kg						
TOTALS		m² 5.65	m²	EA. 1	m²							m 41.4			m 41.4					kg			EA.	kg				EA.	EA.	kg			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

ARCHIVED IN DPR

PROJECT :	PROJECT NO. :
CAVENDISH - WEATHERSFIELD	STP 966I(I)S

DESIGN FILE NAME: /pave/95cl34/pcl34.dgn
IPARM FILE NAME: pcl34t01.i
PLOT DATE: 27-JAN-2006
SURVEYED BY: CLD Inc.
SURVEY DATE: 06/97
SQUAD LEADER: JAW
DRAWN BY: JPC
SHEET: 23 OF 32