STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.9	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																								
STA 0+884 LT		1	750	750	0.56						1			X			X																	E-153M
		1	600	750	0.45																													E-146M
STA 0+952 LT		1	750	750	0.56						1			X			X																	E-153M
STA 1+050 LT	SCHOOL	1	600	200	0.12						1			X			X																	E-153M
	SPEED LIMIT 25	1	600	750	0.45																													E-142M
	WHEN CHILDREN ARE PRESENT	1	600	250	0.15																													E-153M
STA 1+012 LT	STOP 1310 1406 0062	1	750	750	0.56		1				1			X			X																BACK TO BACK		E-143M
STA 1+012 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X			X																	E-141M
STA 1+225 RT		1	750	750	0.56						1			X			X																	E-152M
STA 1+242 LT	TWENTY MILE STREAM RD.						1				1			X			X																SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3 M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 1310 1406 0077	1	750	750	0.56		1																									BACK TO BACK		E-143M
STA 1+252 LT	SPEED LIMIT 35	1	600	750	0.45						1			X			X																	E-142M
	$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS	1	600	750	0.45																													E-144M
TOTALS		m² 5.32	m²	EA. 3	m²							m 36.8			m 36.8				EA	kg			EA.	kg				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

ARCHIVED IN DPR

PROJECT :	PROJECT NO. :
CAVENDISH - WEATHERSFIELD	STP 966I(I)S
DESIGN FILE NAME: /pave/95cl34/pcl34.dgn	
IPARM FILE NAME: pcl34t02.i	PLOT DATE: 27-JAN-2006
SURVEYED BY: CLD Inc.	SURVEY DATE: 06/97
SQUAD LEADER: JAW	DRAWN BY: JPC
	SHEET: 24 OF 32