STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.9	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
												OPTION ITEMS																									
STA 1+252 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X			X																		E-141M
STA 1+454 LT		1	750	750	0.56						1			X			X																		E-152M
STA 2+752 LT	STONEWAY						1				1			X			X																SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3 M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 1310 1406 0171	1 1	750 150	750 200	0.56 0.03																											BACK TO BACK		E-143M E-138M
STA 2+762 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X			X																		E-141M
	NO OUTLET	1	750	750	0.56																													29	
STA 3+070 LT	GAY'S HILL						1				1			X			X																SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3 M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 1310 1406 0191	1 1	750 150	750 200	0.56 0.03																											BACK TO BACK		E-143M E-138M
STA 3+080 LT	LEGAL LOAD LIMIT 24,000 POUNDS; R 12AM TO 7AM DEC 1-APR 1	1 1	600 300	750 450	0.45 0.14						1			X			X															BACK TO BACK	29	E-141M
STA 3+274 LT	STOP 1310 1406 0213	1	750	750	0.56		1				1			X			X															BACK TO BACK		E-143M
STA 3+284 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X			X																		E-141M
STA 3+358 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X			X																		E-141M
STA 3+368 RT	STOP 1310 1406 0209	1 1	750 150	750 200	0.56 0.03						1			X			X															BACK TO BACK		E-143M E-138M
STA 3+419 LT	STOP 1310 1406 0215	1 1	750 150	750 200	0.56 0.03						1			X			X															BACK TO BACK		E-143M E-138M
												m	m	50.6	m	m	50.6		EA	kg	kg	kg		kg	kg	kg	kg							
TOTALS			m² 6.43	m²	EA. 3	m²						m 50.6			m 50.6					kg			EA.	kg				EA.	EA.	kg				

ARCHIVED IN DPR

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT :	PROJECT NO. :
CAVENDISH - WEATHERSFIELD	STP 966I(I)S
DESIGN FILE NAME: /pave/95cl34/pcl34.dgn	
IPARM FILE NAME: pcl34t03.i	PLOT DATE: 27-JAN-2006
SURVEYED BY: CLD Inc.	SURVEY DATE: 06/97
SQUAD LEADER: JAW	DRAWN BY: JPC
	SHEET: 25 OF 32