STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
											OPTION ITEMS																								
STA 7+597 RT	LEGAL LOAD LIMIT 16,000 POUNDS	1	600	750	0.45						1			X			X																	E-141M
STA 7+607 RT	STOP 1310 1406 0472	1 1	750 150	750 200	0.56 0.03						1			X			X															BACK TO BACK		E-143M E-138M
WEATHERSFIELD																																		
STA 1+604 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X			X																	E-141M
STA 1+614 RT	STOP 1310 1420 0100	1 1	750 150	750 200	0.56 0.03						1			X			X															BACK TO BACK		E-143M E-138M
STA 1+680 LT	STOP 1310 1420 0105	1	750	750	0.56		1				1			X			X															BACK TO BACK		E-143M
STA 1+690 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X			X																	E-141M
STA 2+113 RT	STOP 1310 1420 0132	1	1200	1200	1.44		1				2			X			X																	E-143M
	SUBTOTALS SHEET 23				5.65		1							41.4			41.4																	
	SUBTOTALS SHEET 24				5.32		3							36.8			36.8																	
	SUBTOTALS SHEET 25				6.43		3							50.6			50.6																	
	SUBTOTALS SHEET 26				6.18		2							55.2			55.2																	
	SUBTOTALS SHEET 27				4.10		5							36.8			36.8																	
	SUBTOTALS SHEET 28				4.53		2							36.8			36.8																	
												m	m	m 257.6	m	m	m 257.6		EA	kg	kg	kg		kg	kg	kg	kg							
	PROJECT TOTALS				m² 32.21	m²	EA. 16	m²				m 257.6			m 257.6					kg			EA.	kg				EA.	EA.	kg				

ARCHIVED IN DPR

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT : CAVENDISH - WEATHERSFIELD	PROJECT NO. : STP 966I(I)S
DESIGN FILE NAME: /pave/95cl34/pcl34.dgn	
IPARM FILE NAME: pcl34t06.i	PLOT DATE: 27-JAN-2006
SURVEYED BY: CLD Inc.	SURVEY DATE: 06/97
SQUAD LEADER: JAW	DRAWN BY: JPC
	SHEET: 28 OF 32