STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 3

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

				FULL C.E.	EROSION CONTROL	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
				-	-	175	175	m	DURABLE 200 mm WHITE LINE (THERMOPLASTIC)	646.42	6
				-	-	30	30	m	DURABLE 600 mm STOP BAR (THERMOPLASTIC)	646.46	3.3
				-	-	29	29	EA	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50	-
				-	-	125	125	m	DURABLE CROSSWALK MARKINGS W/DIAGONAL LINES (THERMOPLASTIC) (MOD.)	646.51	4
				-	-	8400	8400	m	TEMPORARY 100 mm WHITE LINE (PAINT)	646.60	405
				-	-	8500	8500	m	TEMPORARY 100 mm YELLOW LINE (PAINT)	646.61	436
				-	-	60	60	m	TEMPORARY 600 mm STOP BAR (PAINT)	646.66	6.6
				-	-	58	58	EA	TEMPORARY LETTER OR SYMBOL (PAINT)	646.70	-
				-	-	250	250	m	TEMPORARY CROSSWALK MARKINGS W/DIAGONAL LINES (PAINT) (MOD.)	646.71	8
				-	-	650	650	EA	LINE STRIPING TARGETS	646.76	29
				-	2400	-	2400	m²	GEOTEXTILE FOR SILT FENCE	649.51	110
				-	-	40	40	kg	SEED	651.15	EST.
				-	-	250	250	kg	FERTILIZER	651.18	EST.
				-	-	2	2	t	AGRICULTURAL LIMESTONE	651.20	EST.
				-	-	2	2	t	HAY MULCH	651.25	EST.
				-	-	430	430	m³	TOPSOIL	651.35	16
				-	1	-	1	LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10	-
				-	120	-	120	HR	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.20	EST.
				-	1	-	1	LU	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30	
				-	10	-	10	m²	EROSION MATTING	654.10	-
				-	-	19	19	m²	TRAFFIC SIGNS, TYPE A	675.20	0.94
									BEGIN SIGN POST OPTION ITEMS		
				-	-	154	154	m	FLANGED CHANNEL SIGN POST	675.301	6.8
				-	-	154	154	m	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341	6.8
									END SIGN POST OPTION ITEMS		
				-	-	46	46	EA	REMOVING SIGNS	675.50	-
				-	-	11	11	EA	ERECTING SALVAGED SIGNS	675.60	-
				-	-	1	1	LU	PRICE ADJUSTMENT - FUEL (N.A.B.I.)	690.50	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: NORTH BENNINGTON
PROJECT NUMBER: STP 9646(1)S

FILE NAME: /pave/95d104/pd104.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
pd104qs3.1

PLOT DATE: 30-AUG-2010 12:29
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 9 OF 151