STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	NEW & SALVAGED SIGNS: EA	SIGN DIMENSIONS: WIDTH (mm)	SIGN DIMENSIONS: HEIGHT (mm)	NEW & SALVAGED SIGNS: "A"	"B"	SALV SIGN	SALV TIS	EXIST POST: RETAIN	EXIST POST: SALVAGE	OPTION ITEMS: NO. OF POSTS	FLANGED CHANNEL kg/m: 1.7	FLANGED CHANNEL kg/m: 3.0	FLANGED CHANNEL kg/m: 4.5	SQUARE STEEL (mm) kg/m: 45 / 2.8	SQUARE STEEL (mm) kg/m: 51 / 3.2	SQUARE STEEL (mm) kg/m: 64 / 5.0	ANCHOR	SLEEVE	NEW SIGN POSTS: TUBULAR ALUMINUM Ø (mm) kg/m: 75 / 1.9	TUBULAR ALUMINUM Ø (mm) kg/m: 100 / 2.5	TUBULAR ALUMINUM Ø (mm) kg/m: 100 MOD / 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) kg/m: 75 / 11.3	TUBULAR STEEL Ø (mm) kg/m: 90 / 13.6	TUBULAR STEEL Ø (mm) kg/m: 100 / 16.1	TUBULAR STEEL Ø (mm) kg/m: 125 / 21.8	W-SHAPE STEEL FTG. SIZE: 600 mm	W-SHAPE STEEL FTG. SIZE: 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
												OPTION ITEMS																							
NO. BENNINGTON: VT. ROUTE 67A 3+434.0, LT	BRIDGE 3 VT 67A	1	150	200	0.03						1	X 2.32			X			X															SIGN ID CODE VD-701		E-134
3+440.0, RT	SPEED LIMIT 35	1	600	750	0.45						1			X 4.62		X		X															SIGN ID CODE R2-1		E-142
	STATE HIGHWAY ENDS	1	600	450	0.27																												SIGN ID CODE VR-038		E-141
	THROUGH WAY ENDS HERE	1	600	600	0.36																												SIGN ID CODE VR-040		E-141
3+440.0, LT	SPEED LIMIT 30	1	600	750	0.45						1			X 4.54		X		X															SIGN ID CODE R2-1		E-142
	STATE HIGHWAY BEGINS	1	600	450	0.27																												SIGN ID CODE VR-039		E-141
	THROUGH WAY BEGINS HERE	1	600	600	0.36																												SIGN ID CODE VR-041		E-141
3+465.0, LT		1	750	750	0.56						1			X 4.17		X		X															SIGN ID CODE W11-2		E-152
		1	600	300	0.18																												SIGN ID CODE W16-7P		E-152
3+465.0, RT		1	750	750	0.56						1			X 4.17		X		X															SIGN ID CODE W11-2		E-152
		1	600	300	0.18																												SIGN ID CODE W16-7P		E-152
3+560.0, LT	NARROW BRIDGE	1	750	750	0.56						1			X 3.99		X		X															SIGN ID CODE W5-2		E-154
3+574.9, RT	0671 0202 0223	1	150	250	0.04		1				1	X 2.44			X			X															NEW ~~SALVAGED~~ SIGN TO BE MOUNTED ON NEW POST.	-	-
												m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg							
												~~9.2~~ 4.76		~~23.0~~ 21.49	~~9.2~~ 0	~~23.0~~ 0																		
TOTALS		m^2 ~~4.23~~ 4.27	m^2	EA ~~1~~ 0	m^2			m ~~32.2~~ 26.25		m ~~32.2~~ 0		kg	EA	kg	EA	EA	kg																		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
NORTH BENNINGTON	STP 9646(I)S

DESIGN FILE NAME: /pave/95dl04/pdl04.dgn
IPARM FILE NAME: pdl04tssl.i
SURVEYED BY: L.R.S.C.
SQUAD LEADER: T.P.K.
PLOT DATE:30-AUG-2010 12:3
SURVEY DATE: 4/2003
DRAWN BY: C.A.K.
SHEET: 109 OF 151