STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	OPTION ITEMS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 45 2.8	51 3.2	64 5.0	ANCHOR	SLEEVE	NEW SIGN POSTS TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																										
NO. BENNINGTON: VT. ROUTE 67A 3+600.0, LT		1	750	750	0.56						1			X 4.27		X		X															SIGN ID CODE W11-2		E-152
	AHEAD	1	600	300	0.18																													113	
667.0 3+~~640.0~~, LT		1	750	750	0.56						1			X 4.71		X		X															SIGN ID CODE W1-1R		E-151
	25 MPH	1	450	450	0.20																												SIGN ID CODE W13-1		E-155
3+878.5, LT	067-1 0202 024-1	1	150	250	0.04		1				1	X 2.44			X			X															NEW ~~SALVAGED~~ SIGN TO BE MOUNTED ON NEW POST.	-	-
668.0 4+~~697.0~~, LT		1	600	600	0.36						1			X 4.23		X		X															SIGN ID CODE R8-3A		E-143
	END	1	600	300	0.18																												SIGN ID CODE M4-6		E-140
4+960.0, LT		1	600	600	0.36						1			X 3.81		X		X															SIGN ID CODE R8-3A		E-143
5+012.0, RT	PARK - McCULLOUGH HISTORIC HOUSE ← / BENNINGTON HEAD START ←						2				2			4.97 X 4.97		X		X															SALVAGED SIGNS TO BE MOUNTED ON NEW POSTS.	-	-
5+100.0, RT		1	900	900	0.81						2			3.94 X 3.94		X		X																113	
5+130.0, RT		1	750	750	0.56						1			X 4.67		X		X															SIGN ID CODE W11-2		E-152
	AHEAD	1	600	300	0.18																													113	
5+165.0 RT	SPEED LIMIT 25	1	600	750	0.45						1			X 4.29		X		X															SIGN ID CODE R2-1		E-142
												m ~~4.6~~ 2.44	m	m ~~46.0~~ 43.8	m ~~4.6~~ 0	m ~~46.0~~ 0	m		EA	kg	kg	kg		kg	kg	kg	kg							
TOTALS		m^2 ~~4.40~~ 4.45	m^2	EA ~~3~~ 2	m^2							m ~~50.6~~ 46.74			m ~~50.6~~ 0					kg	EA	kg												

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: NORTH BENNINGTON	PROJECT NO.: STP 9646(I)S
DESIGN FILE NAME: /pave/95dI04/pdI04.dgn	
IPARM FILE NAME: pdI04ss2.I	PLOT DATE:30-AUG-2010 I2:3
SURVEYED BY: L.R.S.C.	SURVEY DATE: 4/2003
SQUAD LEADER: T.P.K.	DRAWN BY: C.A.K.
	SHEET: II0 OF I5I