STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	OPTION ITEMS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 45 2.8	51 3.2	64 5.0	ANCHOR	SLEEVE	NEW SIGN POSTS TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																										
NO. BENNINGTON: VT. ROUTE 67A 5+197.0, RT	STOP						1				1			X 4.02		X		X																INSTALL SALVAGED SIGN ON NEW POST.	-	-
5+209.0, RT	YIELD 900x900x900 / DO NOT ENTER	1 1	 750	 750	0.81 0.56						1			X 4.28		X		X																SIGN ID CODE RI-2 SIGN ID CODE R5-1 BACK-TO-BACK		E-146 E-143
	ONE WAY / ONE WAY	1 1	900 900	300 300	0.27 0.27																												SIGN ID CODE R6-1L SIGN ID CODE R6-1R BACK-TO-BACK		E-142 E-142
5+243.3, RT	SAGE ST						1				1			X 3.97		X		X																SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP	1	750	750	0.56																												SIGN ID CODE RI-1		E-143
5+218.0 LT	NO PARKING THIS SIDE						1				1			X 3.79																				INSTALLED SALVAGED SIGN ON NEW POST		
5+270.0, LT		1	750	750	0.56						1			X 4.23		X		X																SIGN ID CODE W11-2		E-152
	AHEAD	1	600	300	0.18																														113	
RIVER ROAD: RI+010.0, LT	RIVER ROAD						1				1			X 3.97		X		X																SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP	1	750	750	0.56																												SIGN ID CODE RI-1		E-143
HILLSIDE STREET: HI+014.5, LT	HILLSIDE ST						1				1			X 4.37		X		X																SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP	1	750	750	0.56																												SIGN ID CODE RI-1		E-143
RI+028 RT	COVERED BRIDGE TREATMENT PLANT	1 1	450 900	300 300	0.14 0.27						1			X 4.37																				INSTALL NEW SIGNS ON NEW POST		
HI+018.7, RT	SPEED LIMIT 30	1	600	750	0.45						1			X 3.99		X		X																SIGN ID CODE R2-1		E-142
RI+029 RT	PLAY GROUND										1			X 4.37																				INSTALLED SALVAGED SIGN ON NEW POST		
	SHEET SUBTOTALS			5.19	~~4.78~~		~~4~~	6				-	41.36	~~32.2~~	-	32.2																				
	SHEET 109 SUBTOTALS			4.27	~~4.23~~		~~1~~	0			4.76	~~9.2~~	21.44	~~23.0~~	9.2	23.0																				
	SHEET 110 SUBTOTALS			4.48	~~4.40~~		~~3~~	1			2.44	~~4.6~~	43.8	~~46.0~~	4.6	46.0																				
	SHEET 111 SUBTOTALS				4.65		3					-	28.44	~~32.2~~	-	32.2																				
	ROUNDING			0	~~0.94~~		-					~~0.2~~ 0		~~6.6~~ 0	0.2	6.6																				
												m 14	m	m 140	m 14	m 140	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS					m^2 ~~19.0~~ 18.55	m^2	EA 11	m^2				m ~~154~~ 142.24			m 154					kg	EA	kg		EA	EA	kg									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: NORTH BENNINGTON	PROJECT NO.: STP 9646(I)S
DESIGN FILE NAME: /pave/95dl04/pdl04.dgn	
IPARM FILE NAME: pdl04tss4.I	PLOT DATE:30-AUG-2010 12:3
SURVEYED BY: L.R.S.C.	SURVEY DATE: 4/2003
SQUAD LEADER: T.P.K.	DRAWN BY: C.A.K.
	SHEET: 112 OF 151