

QUANTITY SHEET 2



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
						520				520		HR	EMPLOYEE TRAINEESHIP	634.10				
					1					1		LS	MOBILIZATION / DEMOBILIZATION	635.11				
					1					1		LS	TRAFFIC CONTROL	641.10				
					240					240		M	100 MM WHITE LINE	646.20				
					240					240		M	100 MM YELLOW LINE	646.21				
							120			120		SM	GEOTEXTILE FOR SILT FENCE	649.51				
							10			10		KG	SEED	651.15				
							60			60		KG	FERTILIZER	651.18				
							0.5			0.5		T	AGRICULTURAL LIMESTONE	651.20				
							0.5			0.5		T	HAY MULCH	651.25				
					20					20		CM	TOPSOIL	651.35				
							1			1		LS	EPSC PLAN	652.10				
							60			60		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							50			50		CM	VEHICLE TRACKING PAD	653.35				
							200			200		M	PROJECT DEMARCATION FENCE	653.55				
					1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
					33					33		M	SPECIAL PROVISION (ALUMINUM APPROACH RAILING, ANODIZED)	900.640				
								20		20		M	SPECIAL PROVISION (BRIDGE RAILING, ANODIZED 3 RAIL ALUMINUM)	900.640				
								20		20		M	SPECIAL PROVISION (BRIDGE RAILING, ANODIZED ALUMINUM/PEDESTRIAN)	900.640				