# APPROXIMATE SUMMARY OF QUANTITIES

* – POSSIBLE ON-PROJECT STAGING AREA

| | | | STAGING AREA * | CITY WATER AND SEWER NON-PART. | CITY WATER AND SEWER PART. | E & C | EROSION CONTROL | ROADWAY PARTIC. | TRAINING | STRUCTURES | LANDSCAPING | QUANTITY GRAND TOTAL | UNIT | DESCRIPTION OF ITEMS | ITEM NUMBER | ROUNDING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | | | BEGIN OPTION BID ITEMS | | |
| | | | | | | | | | | | | | | OPTION FOR 12" PIPE | | |
| | | | | | | | | 50 | | | | 50 | LF | 12" PCCSP 0.064 (2–2/3x1/2) | 601.0405 | 16 |
| | | | | | | | | 50 | | | | 50 | LF | 12" CAAP 0.060 (2–2/3x1/2) | 601.0205 | 16 |
| | | | | | | | | 50 | | | | 50 | LF | 12" RCP CLASS III | 601.0805 | 16 |
| | | | | | | | | 50 | | | | 50 | LF | 12" CPEP (SL) | 601.2605 | 16 |
| | | | | | | | | | | | | | | OPTION FOR 18" PIPE | | |
| | | | | | | | | 9,000 | | | | 9,000 | LF | 18" PCCSP 0.064 (2–2/3x1/2) | 601.0415 | 89 |
| | | | | | | | | 9,000 | | | | 9,000 | LF | 18" CAAP 0.060 (2–2/3x1/2) | 601.0215 | 89 |
| | | | | | | | | 9,000 | | | | 9,000 | LF | 18" RCP CLASS III | 601.0815 | 89 |
| | | | | | | | | 9,000 | | | | 9,000 | LF | 18" CPEP (SL) | 601.2615 | 89 |
| | | | | | | | | | | | | | | OPTION FOR 24" PIPE | | |
| | | | | | | | | 2,250 | | | | 2,250 | LF | 24" PCCSP 0.064 (2–2/3x1/2) | 601.0425 | 56 |
| | | | | | | | | 2,250 | | | | 2,250 | LF | 24" CAAP 0.060 (2–2/3x1/2) | 601.0225 | 56 |
| | | | | | | | | 2,250 | | | | 2,250 | LF | 24" RCP CLASS III | 601.0825 | 56 |
| | | | | | | | | 2,250 | | | | 2,250 | LF | 24" CPEP (SL) | 601.2620 | 56 |
| | | | | | | | | | | | | | | OPTION FOR 18" END SECTIONS | | |
| | | | | | | | | 2 | | | | 2 | EA | 18" CSPES 0.064 (2–2/3x1/2) | 601.6015 | – |
| | | | | | | | | 2 | | | | 2 | EA | 18" CAAPES 0.060 (2–2/3x1/2) | 601.6215 | – |
| | | | | | | | | 2 | | | | 2 | EA | 18" RCPES CLASS III | 601.6815 | – |
| | | | | | | | | 2 | | | | 2 | EA | 18" CPEPES | 601.7015 | – |
| | | | | | | | | | | | | | | OPTION FOR 24" END SECTIONS | | |
| | | | | | | | | 15 | | | | 15 | EA | 24" CSPES 0.064 (2–2/3x1/2) | 601.6025 | – |
| | | | | | | | | 15 | | | | 15 | EA | 24" CAAPES 0.060 (2–2/3x1/2) | 601.6225 | – |
| | | | | | | | | 15 | | | | 15 | EA | 24" RCPES CLASS III | 601.6825 | – |
| | | | | | | | | 15 | | | | 15 | EA | 24" CPEPES | 601.7020 | – |
| | | | | | | | | | | | | | | END OPTION BID ITEMS | | |
| | | | | | | | | 1 | | | | 1 | EA | 12" CSPES .064 (2–2/3 X 1/2) | 601.6005 | – |
| | | | | | | | | 58 | | | | 58 | EA | PRECAST REINFORCED CONC. CATCH BASIN WITH C.I. GRATE (48") | 604.20 | – |
| | | | | | | | | 5 | | | | 5 | EA | PRECAST REINFORCED CONC. CATCH BASIN WITH C.I. GRATE (72") | 604.20 | – |
| | | | | | | | | 6 | | | | 6 | EA | PRECAST REINFORCED CONC. MANHOLE WITH C.I. COVER (48") | 604.21 | – |
| | | | | 12 | 1 | | | | | | | 13 | EA | SANITARY SEWER MANHOLE (48") | 604.22 | – |
| | | | | 1 | | | | | | | | 1 | EA | SANITARY SEWER MANHOLE (72") | 604.22 | – |
| | | | | | | | | 7 | | | | 7 | EA | PRC DROP INLET WITH CAST IRON GRATE | 604.30 | – |
| | | | | 17 | 2 | | | 8 | | | | 27 | EA | CHANGING ELEV OF DROP INLETS, CATCH BASINS, OR MANHOLES | 604.40 | – |
| | | | | | | | | 12,000 | | | 1,500 | 13,500 | LF | 6" UNDERDRAIN | 605.10 | 188 |
| | | | | | | | | 55 | | | | 55 | HR | BULLDOZER RENTAL, TYPE 1 | 608.10 | EST |
| | | | | | | | | 55 | | | | 55 | HR | POWER GRADER RENTAL | 608.15 | EST |

# QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

## DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | DESCRIPTION OF ITEMS |
|---|---|---|

## TYPE OF CONSTRUCTION

| STATIONS FROM | STATIONS TO | PAVEMENT WIDTHS 74'–0" C – C | TAPER | | | | | | EQUATIONS + | EQUATIONS – |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | |
| TOTALS | | 5,680' | | | | | | | | |

| STATIONS | | FEET | MILES | REMARKS |
|---|---|---|---|---|
| | | | | |
| TOTALS | | 7,303 | 1.39 | |

PROJECT NAME: SHELBURNE

PROJECT NUMBER: NH–EGC–019=4 (28)

4/4/03

QUANTITY DRAWING NO. 2

SHEET 15 OF 283 SHEETS