APPROXIMATE SUMMARY OF QUANTITIES

* – POSSIBLE ON-PROJECT STAGING AREA

STAGING AREA *	CITY WATER AND SEWER NON-PART.	CITY WATER AND SEWER PART.	E & C	EROSION CONTROL	ROADWAY PARTIC.	TRAINING	STRUCTURES	LANDSCAPING	QUANTITY GRAND TOTAL	UNIT	DESCRIPTION OF ITEMS	ITEM NUMBER	ROUNDING
								21	21	EA	DECIDUOUS TREES (CLEVELAND SELECT PEAR)	656.30	–
								3	3	EA	DECIDUOUS TREES (PRINCETON UPRIGHT SCHOLAR TREE)	656.30	–
								24	24	EA	DECIDUOUS TREES (PATMORE GREEN ASH)	656.30	–
								22	22	EA	DECIDUOUS TREES (SUMMIT GREEN ASH)	656.30	–
								2	2	EA	DECIDUOUS TREES (RED OAK)	656.30	–
								40	40	EA	DECIDUOUS SHRUBS (MYSTIC MEIDILAND ROSE)	656.35	
					4				4	EA	REST AREA BENCH (BUS SHELTER)	658.20	–
					900				900	SF	TRAFFIC SIGNS (TYPE A)	675.20	69
					1,800				1,800	LF	FLANGED CHANNEL SIGN POSTS	675.301	85
					83				83	EA	REMOVING SIGNS	675.50	–
					19				19	EA	ERECTING SALVAGED SIGNS	675.60	–
					50				50	EA	DELINEATORS WITH STEEL POSTS	676.10	–
					100				100	EA	DELINEATORS WITH FLEXIBLE POSTS (MOD)	676.20	EST
					1				1	EA	TRAFFIC CONTROL SIGNAL SYSTEM – INTERSECTION (ALLEN RD)	678.15	–
					1				1	EA	TRAFFIC CONTROL SIGNAL SYSTEM – INTERSECTION (HARBOR VIEW RD)	678.15	–
					1				1	EA	TRAFFIC CONTROL SIGNAL SYSTEM – INTERSECTION (BARTLETT BAY RD)	678.15	–
					1				1	EA	TRAFFIC CONTROL SIGNAL SYSTEM – INTERSECTION (HOLMES RD)	678.15	–
					6,000				6,000	LF	INTERCONNECTING CABLE (MOD) (2" PVC)	678.20	551
					1,800				1,800	LF	ELECTRICAL CONDUIT (2" PVC)	678.21	84
					6,000				6,000	LF	ELECTRICAL CONDUIT (3" PVC)	678.21	471
					3,000				3,000	LF	VEHICLE LOOP DETECTOR	678.22	67
					12,000				12,000	LF	WIRED CONDUIT (2" PVC)	678.23	89
					50				50	LF	WIRED CONDUIT (2 1/2" PVC)	678.23	10
					35				35	EA	JUNCTION BOX	678.26	–
					8				8	EA	PULL BOX – DOUBLE	678.27	–
					650				650	LF	ELECTRICAL CONDUIT SLEEVE (6" PVC)	678.30	24
					1,200				1,200	LF	ELECTRICAL CONDUIT SLEEVE (8" PVC)	678.30	26
					250				250	LF	ELECTRICAL CONDUIT SLEEVE (12" PVC)	678.30	25
					1				1	EA	TEMPORARY TRAFFIC SIGNAL SYSTEM (ALLEN ROAD)	678.40	–
					1				1	EA	TEMPORARY TRAFFIC SIGNAL SYSTEM (GREEN MOUNTAIN DRIVE)	678.40	–
					1				1	EA	TEMPORARY TRAFFIC SIGNAL SYSTEM (HOLMES ROAD)	678.40	–
					6				6	EA	TEMPORARY DETECTOR	678.42	EST
					61				61	EA	LIGHT POLE BASE	679.21	–
					61				61	EA	BREAKAWAY FEATURE FOR LIGHT POLE	679.23	–
					3				3	EA	REMOVING AND RESETTING LIGHT POLE	679.25	–
					61				61	EA	LIGHT POLE	679.45	–
					61				61	EA	BRACKET ARM	679.47	–
					61				61	EA	LUMINAIRE	679.50	–

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	DESCRIPTION OF ITEMS

TYPE OF CONSTRUCTION

STATIONS		PAVEMENT WIDTHS							EQUATIONS	
FROM	TO	74'–0" C – C	TAPER						+	–
TOTALS		5,680'								

STATIONS		FEET	MILES	REMARKS
TOTALS		7,303	1.39	

PROJECT NAME: SHELBURNE
PROJECT NUMBER: NH–EGC–019=4 (28)

4/4/03

QUANTITY DRAWING NO. 6

SHEET 19 OF 283 SHEETS