STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL TRAFFIC SIGN DETAIL DWG.	STD. SHEET NUMBER
407+81, RT.	RIGHT LANE ONLY 900.57	1	24"	30"	5.00						1			X																					NO. 4	
408+74, LT.	ONE WAY 900.57	1	36"	12"	3.00						1			X																				R6-1R		E-142
409+14, LT.	Magic Hat Brewing Company 2/10 675.60	1	72"	16"				X			2			X																				SALVAGED		
	Allscripts Healthcare Solutions 2/10 675.60	1	72"	16"				X																										SALVAGED		
	Vt. Commons School 4/10 675.60	1	72"	16"				X																										SALVAGED		
409+20, RT.	SPEED LIMIT 40 900.57	1	24"	30"	5.00						1			X																				R2-1		E-142
	0070 0414 0060	1	6"	8"	0.33																													SIGN SHALL FACE NORTHBOUND DIRECTION		E-138
409+62, LT.	ONE WAY 900.57	2	36"	12"	6.00						1			X																				R6-1R (MOUNTED BACK TO BACK)		E-142
409+81, LT.	TRUCK U-TURN 1/4 MILE AHEAD 900.57	1	24"	30"	5.00						1			X																					NO. 3	
410+10, LT.		1	24"	24"			X				1			X																				SALVAGED		
		1	21"	15"			X																										SALVAGED		
410+53, LT.	RIGHT LANE ONLY 900.57	1	24"	30"	5.00						1			X																					NO. 4	
410+77, LT.	ONE WAY 900.57	1	36"	12"	3.00						1			X																				R6-1R		E-142
411+18, LT.	NO PARKING ANY TIME 900.57	1	24"	30"	5.00						1			X																				VR-020 (MODIFY)	NO. 5	
411+65, LT.	900.57	1	24"	30"	5.00						1			X																				R4-7		E-144
	675.20	1	18"	18"	2.25																												OM-1		E-150
												FT 0	FT 0	FT 164	FT	FT	FT		FT	FT	FT	FT		FT	FT	FT	FT								
TOTALS		SF 52	SF 0	EA. 2	EA. 3							FT 164			FT					FT			EA.	FT				EA.	EA.	FT					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

AS-BUILT LEGEND

———— PAVEMENT \OTHER AS-BUILTS

AS-BUILT REVISIONS

NO.	DATE	DESCRIPTION
1.	6/29/06	NOTES ADDED PER ENGINEERS MARK UPS

NOTE:
1. ITEM # 675.20 ORIGINAL ENCAPSULATED SHEETING
2. ITEM # 900.57 MODIFIED TO ENCAPSULATED SHEETING BY CO# 21

4/4/03

SHELBURNE – SOUTH BURLINGTON

SURVEYED BY V.S.C. INC. DATE _____
DRAWN BY E.A.A. INC. DATE _____
TRACED BY E.A.A. INC. DATE _____

PROJECT NH-EGC-019-4(28)
SIGN SUMMARY DRAWING NO. 8
SHEET NO. 110 OF 283

C:\6330008 (US Rte 7 Shelburne Rd)\AS-BUILTS\SIGNING-STRIPING\SIGN DATA\SD-08_4.DWG, 6/30/2006 10:13:02 AM