STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL TRAFFIC SIGN DETAIL DWG.	STD. SHEET NUMBER
421+25, RT.	HOLMES RD 900.57	1	60"	10"	4.17						2			X																				NO. 2	
419+70	IDX DRIVE 900.57	1	60"	10"	4.17																													NO. 2	
	675.20	2	18"	18"	4.50																												OM-1		E-150
421+76, LT.	RIGHT LANE ONLY 900.57	1	24"	30"	5.00						1			X																				NO. 4	
421+97, LT.	U V M Hort. Farm left at light 1/4 675.60	1	72"	16"				X			2			X																			SALVAGED		
	AAMCO Transmission left at light 1/4 675.60	1	72"	16"				X																									SALVAGED		
422+38, LT.	NO PARKING IN BUS LANE 900.57	1	24"	30"	5.00						1			X																			VR-020 (MODIFY)	NO. 5	
	CCTA BUS STOP 675.60	1																															PROVIDED BY OTHERS		
422+48, RT.	REDUCED SPEED AHEAD 900.57	1	24"	30"	5.00						1			X																			R2-5A		E-142
423+07, LT.	900.57	1	24"	30"	5.00						1			X																			R4-7		E-144
	675.20	1	18"	18"	2.25																												OM-1		E-150
	LEFT TURN OR U TURN 900.57	1	24"	30"	5.00																													NO. 3	
	0070 0414 0087 900.57	1	6"	8"	0.33																												SIGN SHALL FACE NORTHBOUND DIRECTION		E-138
423+35, LT.	ONLY 675.20	1	30"	36"	7.50																												MOUNT ON MAST ARM (CANTILEVER #13)	NO. 2	
	HOLMES RD 675.20	2	72"	12"	12.00																												MOUNT ON MAST ARM (CANTILEVER #13)	NO. 1	
423+40, RT.	900.57	1	24"	24"	4.00						1			X																			R3-1		E-143
												FT 0	FT 0	FT 119	FT	FT	FT		FT	FT	FT	FT		FT	FT	FT	FT								
	TOTALS				SF 64	SF 0	EA. 0	EA. 2				FT 119			FT					FT			EA.		FT			EA.	EA.	FT					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

AS-BUILT LEGEND

PAVEMENT \OTHER AS-BUILTS

AS-BUILT REVISIONS

NO.	DATE	DESCRIPTION
1.	6/29/06	NOTES ADDED PER ENGINEERS MARK UPS

NOTE:
1. ITEM # 675.20 ORIGINAL ENCAPSULATED SHEETING
2. ITEM # 900.57 MODIFIED TO ENCAPSULATED SHEETING BY CO# 21

4/4/03

SHELBURNE – SOUTH BURLINGTON

SURVEYED BY V.S.C. INC. DATE
DRAWN BY E.A.A. INC. DATE
TRACED BY E.A.A. INC. DATE

PROJECT NH-EGC-019-4(28)
SIGN SUMMARY DRAWING NO. 10
SHEET NO. 112 OF 283

C:\6330008 (US Rte 7 Shelburne Rd)\AS-BUILTS\SIGNING-STRIPING\SIGN DATA\SD-10_4.DWG, 6/30/2006 10:22:47 AM