STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

LE MARKER, STATION, OR GN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL ø (in) 3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL TRAFFIC SIGN DETAIL DWG.	STD. SHEET NUMBER
23+91, LT.	SHELBURNE RD 675.20	1	90"	12"	7.50																													MOUNT ON MAST ARM (CANTILEVER #15)	NO. 1	
23+92, RT.	SHELBURNE RD 675.20	1	90"	12"	7.50																													MOUNT ON MAST ARM (CANTILEVER #14)	NO. 1	
24+32, RT.	ONLY 675.20	1	30"	36"	7.50																													MOUNT ON MAST ARM (CANTILEVER #16)	NO. 2	
	IDX DR 675.20	2	42"	12"	7.00																													MOUNT ON MAST ARM (CANTILEVER #16)	NO. 1	
25+51, RT.	NO PARKING IN BUS LANE 900.57	1	24"	30"	5.00						1			X																			VR-020 (MODIFY)	NO. 5	
	CCTA BUS STOP 675.60	1																															PROVIDED BY OTHERS		
26+35, RT.	RIGHT LANE ONLY 900.57	1	24"	30"	5.00						1			X																				NO. 4	
26+44, RT.	SPEED LIMIT 35 900.57	1	24"	30"	5.00						1			X																			R2-1		E-142
27+29, LT.	END 900.57	1	24"	12"	2.00						1			X																			M4-6		E-140
	CENTER LANE ONLY 900.57	1	24"	30"	5.00																												R3-9B		E-140
27+10, RT.	LANE ENDS 900.57	1	24"	30"	5.00						1			X																				NO. 4	
27+29, RT.	BEGIN 900.57	1	24"	12"	2.00						1			X																			M4-11		E-140
	CENTER LANE ONLY 900.57	1	24"	30"	5.00																												R3-9B		E-140
27+95, RT.	SHELBURNE RD (mirrored) 900.57	1	42"	9"	2.63						1			X																			RURAL TOP MOUNTED – TEXT ON BOTH SIDES	NO. 1	E-123
	IMPERIAL DR (mirrored) 900.57	1	36"	9"	2.25																												RURAL TOP MOUNTED – TEXT ON BOTH SIDES	NO. 1	E-123
28+26, LT.	LANE AHEAD 900.57	1	24"	30"	5.00						1			X																			AS-BUILT LEGEND: PAVEMENT \OTHER AS-BUILTS	NO. 4	
												FT 0	FT 0	FT 98	FT	FT	FT		FT	FT	FT	FT		FT	FT	FT	FT								
	TOTALS				SF 73	SF 0	EA. 0	EA. 0				FT 98			FT					FT			EA.	FT				EA.	EA.	FT					

INAL POST LENGTHS ARE TO BE DETERMINED
N THE FIELD. POST SIZES ARE COMPUTED
ASED ON INFORMATION FURNISHED ON THE
TANDARD SHEETS AND THE TRAFFIC & SAFETY
IVISION'S "SIGN POST DESIGN GUIDELINE."

AS-BUILT REVISIONS

NO.	DATE	DESCRIPTION
1.	6/29/06	NOTES ADDED PER ENGINEERS MARK UPS

NOTE:
1. ITEM # 675.20 ORIGINAL ENCAPSULATED SHEETING
2. ITEM # 900.57 MODIFIED TO ENCAPSULATED SHEETING BY CO# 21

4/4/03

SHELBURNE – SOUTH BURLINGTON

SURVEYED BY V.S.C. INC. DATE_____
DRAWN BY E.A.A. INC. DATE_____
TRACED BY E.A.A. INC. DATE_____

PROJECT NH-EGC-019-4(28)
SIGN SUMMARY DRAWING NO. 11
SHEET NO. 113 OF 283

US Rte 7 Shelburne Rd)\AS-BUILTS\SIGNING-STRIPING\SIGN DATA\SD-11_4.DWG, 6/30/2006 10:29:48 AM