APPROXIMATE SUMMARY OF QUANTITIES

* – POSSIBLE ON-PROJECT STAGING AREA

			STAGING AREA *	CITY WATER AND SEWER NON-PART.	CITY WATER AND SEWER PART.	E & C	EROSION CONTROL	ROADWAY PARTIC.	TRAINING	STRUCTURES	LANDSCAPING	QUANTITY GRAND TOTAL	UNIT	DESCRIPTION OF ITEMS	ITEM NUMBER	ROUNDING
														BEGIN OPTION BID ITEMS		
														OPTION FOR 12" PIPE		
								50				50	LF	12" PCCSP 0.064 (2–2/3x1/2)	601.0405	16
								50				50	LF	12" CAAP 0.060 (2–2/3x1/2)	601.0205	16
								50				50	LF	12" RCP CLASS III	601.0805	16
								50				50	LF	12" CPEP (SL)	601.2605	16
														OPTION FOR 18" PIPE		
								9,000				9,000	LF	18" PCCSP 0.064 (2–2/3x1/2)	601.0415	89
								9,000				9,000	LF	18" CAAP 0.060 (2–2/3x1/2)	601.0215	89
								9,000				9,000	LF	18" RCP CLASS III	601.0815	89
								9,000				9,000	LF	18" CPEP (SL)	601.2615	89
														OPTION FOR 24" PIPE		
								2,250				2,250	LF	24" PCCSP 0.064 (2–2/3x1/2)	601.0425	56
								2,250				2,250	LF	24" CAAP 0.060 (2–2/3x1/2)	601.0225	56
								2,250				2,250	LF	24" RCP CLASS III	601.0825	56
								2,250				2,250	LF	24" CPEP (SL)	601.2620	56
														OPTION FOR 18" END SECTIONS		
								2				2	EA	18" CSPES 0.064 (2–2/3x1/2)	601.6015	–
								2				2	EA	18" CAAPES 0.060 (2–2/3x1/2)	601.6215	–
								2				2	EA	18" RCPES CLASS III	601.6815	–
								2				2	EA	18" CPEPES	601.7015	–
														OPTION FOR 24" END SECTIONS		
								15				15	EA	24" CSPES 0.064 (2–2/3x1/2)	601.6025	–
								15				15	EA	24" CAAPES 0.060 (2–2/3x1/2)	601.6225	–
								15				15	EA	24" RCPES CLASS III	601.6825	–
								15				15	EA	24" CPEPES	601.7020	–
														END OPTION BID ITEMS		
								1				1	EA	12" CSPES .064 (2–2/3 X 1/2)	601.6005	–
								58				58	EA	PRECAST REINFORCED CONC. CATCH BASIN WITH C.I. GRATE (48")	604.20	–
								5				5	EA	PRECAST REINFORCED CONC. CATCH BASIN WITH C.I. GRATE (72")	604.20	–
								6				6	EA	PRECAST REINFORCED CONC. MANHOLE WITH C.I. COVER (48")	604.21	–
				12	1							13	EA	SANITARY SEWER MANHOLE (48")	604.22	–
				1								1	EA	SANITARY SEWER MANHOLE (72")	604.22	–
								7				7	EA	PRC DROP INLET WITH CAST IRON GRATE	604.30	–
				17	2			8				27	EA	CHANGING ELEV OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	–
								12,000			1,500	13,500	LF	6" UNDERDRAIN	605.10	188
								55				55	HR	BULLDOZER RENTAL, TYPE I	608.10	EST
								55				55	HR	POWER GRADER RENTAL	608.15	EST

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	DESCRIPTION OF ITEMS

TYPE OF CONSTRUCTION

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS 74'–0" C – C	TAPER						EQUATIONS +	EQUATIONS –
TOTALS		5,680'								

STATIONS		FEET	MILES	REMARKS
TOTALS		7,303	1.39	

PROJECT NAME: SHELBURNE

PROJECT NUMBER: NH–EGC–019=4 (28)

4/4/03

QUANTITY DRAWING NO. 2

SHEET 15 OF 283 SHEETS