APPROXIMATE SUMMARY OF QUANTITIES

* – POSSIBLE ON-PROJECT STAGING AREA

STAGING AREA *	CITY WATER AND SEWER NON-PART.	CITY WATER AND SEWER PART.	E & C	EROSION CONTROL	ROADWAY PARTIC.	TRAINING	STRUCTURES	LANDSCAPING	QUANTITY GRAND TOTAL	UNIT	DESCRIPTION OF ITEMS	ITEM NUMBER	ROUNDING
	573	467							1040	LF	DUCTILE IRON PIPE, CEMENT-LINED (MOD)(8" CL-51)	629.24	–
	4274	512							4786	LF	DUCTILE IRON PIPE, CEMENT-LINED (MOD)(12" CL-51)	629.24	–
	10	2							12	EA	EXTENSION SERVICE BOX AND CURB STOP (3/4" OR 1")	629.25	–
	4								4	EA	EXTENSION SERVICE BOX AND CURB STOP (1 1/2")	629.25	–
	3								3	EA	EXTENSION SERVICE BOX AND CURB STOP (2")	629.25	–
		2							2	EA	GATE VALVE WITH VALVE BOX (6")	629.27	–
	5	3							8	EA	GATE VALVE WITH VALVE BOX (8")	629.27	–
	17	5							22	EA	GATE VALVE WITH VALVE BOX (12")	629.27	–
	11								11	EA	HYDRANT	629.28	–
	8								8	EA	RELOCATE HYDRANT	629.29	–
	2	6							8	EA	TAPPING SLEEVE & VALVE WITH VALVE BOX (8x8)	629.35	–
	1	1							2	EA	TAPPING SLEEVE & VALVE WITH VALVE BOX (12x12)	629.35	–
	7	2							9	EA	CORPORATION STOP (3/4" OR 1")	629.39	–
	3								3	EA	CORPORATION STOP (1 1/2")	629.39	–
	3								3	EA	CORPORATION STOP (2")	629.39	–
	1								1	LS	TRANSFER TO NEW SYSTEM-WATER SYSTEM	629.42	–
	14	4							18	EA	AIR RELEASE-WATER	629.43	–
	3								3	EA	AIR RELEASE-WATER (MOD 1) (AIR RELEASE VALVE AND MANHOLE ASSEMBLY)	629.43	–
		1							1	EA	AIR RELEASE-WATER (MOD 2) (6" BLOWOFF ASSEMBLY)	629.43	–
								1	1	LS	IRRIGATION SYSTEM	629.45	–
					9,000				9,000	HR	UNIFORM TRAFFIC OFFICERS	630.10	360
					18,000				18,000	HR	FLAGGERS	630.15	720
						2,100			2,100	HR	EMPLOYEE TRAINEESHIP	634.10	20
					1				1	LS	MOBILIZATION	635.10	–
					1				1	LS	TRAFFIC CONTROL (MOD)	641.10	–
					4				4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	–
					2				2	EA	PORTABLE ARROW BOARD	641.16	–
					22,000				22,000	LF	4" WHITE LINES	646.20	685
					16,000				16,000	LF	4" YELLOW LINES	646.21	172
					9,000				9,000	LF	DURABLE 4" WHITE LINE (THERMOPLASTIC)	646.40	127
					14,500				14,500	LF	DURABLE 4" YELLOW LINE (THERMOPLASTIC)	646.41	111
					10,600				10,600	LF	DURABLE 6" WHITE LINE (THERMOPLASTIC)	646.414	96
					100				100	LF	DURABLE 8" WHITE LINE (THERMOPLASTIC)	646.42	46

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	DESCRIPTION OF ITEMS

TYPE OF CONSTRUCTION

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS 74'-0" C – C	PAVEMENT WIDTHS TAPER	EQUATIONS +	EQUATIONS –
TOTALS		5,680'			

STATIONS	FEET	MILES	REMARKS
TOTALS	7,303	1.39	

PROJECT NAME: SHELBURNE
PROJECT NUMBER: NH-EGC-019=4 (28)

4/4/03

QUANTITY DRAWING NO. 4

SHEET 17 OF 283 SHEETS