APPROXIMATE SUMMARY OF QUANTITIES

* - POSSIBLE ON-PROJECT STAGING AREA

STAGING AREA *	CITY WATER AND SEWER NON-PART.	CITY WATER AND SEWER PART.	E & C	EROSION CONTROL	ROADWAY PARTIC.	TRAINING	STRUCTURES	LANDSCAPING	QUANTITY GRAND TOTAL	UNIT	DESCRIPTION OF ITEMS	ITEM NUMBER	ROUNDING
					1,200				1,200	LF	DURABLE 8" YELLOW LINE (THERMOPLASTIC)	646.43	65
					600				600	LF	DURABLE 24" STOP BAR (TAPE – TYPE 1)	646.46	73
					299				299	EA	DURABLE LETTER OR SYMBOL (TAPE – TYPE 1)	646.50	–
					850				850	LF	DURABLE CROSSWALK W/ DIAGONAL LINES (TAPE – TYPE 1)	646.51	36
					78,000				78,000	LF	TEMPORARY 4" WHITE LINE	646.60	375
					63,000				63,000	LF	TEMPORARY 4" YELLOW LINE	646.61	390
					1,500				1,500	LF	TEMPORARY 8" YELLOW LINE	646.63	450
					2,500				2,500	LF	TEMPORARY 24" STOP BAR	646.66	340
					300				300	EA	TEMPORARY LETTER OR SYMBOL	646.70	EST
					1,700				1,700	LF	TEMPORARY CROSSWALK W/ DIAGONAL LINES	646.71	EST
					500				500	EA	LINE STRIPING TARGETS	646.76	EST
					20,000				20,000	SF	BLACK PAVEMENT MARKING MASKING TAPE	646.86	–
					10,000				10,000	SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	823
4,500									4,500	SY	GEOTEXTILE FOR ROADBED SEPARATOR (MOD)	649.11	46
							900		900	SY	GEOTEXTILE UNDER STONE FILL	649.31	90
4,500				3,300					7,800	SY	GEOTEXTILE FOR SILT FENCE	649.51	132
					520				520	lbs	SEED	651.15	–
					2,700				2,700	lbs	FERTILIZER	651.18	99
					10				10	Tons	AGRICULTURAL LIMESTONE	651.20	–
					10				10	Tons	HAY MULCH (MOD)	651.25	–
				40					40	EA	HAY BALES FOR EROSION CONTROL	651.26	–
				10					10	EA	HAY BALES FOR EROSION CONTROL (MOD)	651.26	EST
					2,000			500	2,500	CY	TOPSOIL	651.35	256
							400		400	SY	GRUBBING MATERIAL	651.40	60
					1				1	LS	EROSION & SEDIMENT CONTROL PLAN	652.10	EST
					1,000				1,000	HR	MONITORING EROSION & SEDIMENT CONTROL PLAN	652.20	EST
					1				1	LU	FIELD MAINTENANCE OF EROSION & SEDIMENT CONTROL PLAN (NABI)	652.30	EST
				6,500					6,500	SY	EROSION MATTING (SLOPES)	654.10	60
				700					700	SY	EROSION MATTING (DITCHES)	654.10	49
								62	62	EA	DECIDUOUS TREES (TATARIAN MAPLE)	656.30	–
								18	18	EA	DECIDUOUS TREES (SNOWCLOUD SERVICEBERRY)	656.30	–
								21	21	EA	DECIDUOUS TREES (SPRING SNOW CRABAPPLE)	656.30	–
								42	42	EA	DECIDUOUS TREES (HARVEST GOLD CRABAPPLE)	656.30	–
								6	6	EA	DECIDUOUS TREES (IVORY SILK TREE LILAC)	656.30	–

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	DESCRIPTION OF ITEMS

TYPE OF CONSTRUCTION

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS 74'–0" C – C	TAPER						EQUATIONS +	EQUATIONS –
TOTALS		5,680'								

STATIONS	FEET	MILES	REMARKS
TOTALS	7,303	1.39	

PROJECT NAME: SHELBURNE
PROJECT NUMBER: NH-EGC-019=4 (28)
4/4/03

QUANTITY DRAWING NO. 5
SHEET 18 OF 283 SHEETS