STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL TRAFFIC SIGN DETAIL DWG.	STD. SHEET NUMBER
376+20, LT.	TOWN OF SHELBURNE FIREARMS DISCHARGE ORDINANCE IN EFFECT CONTACT POLICE DEPT BEFORE HUNTING 675.60	1	X"	X"			X				1			X																			SALVAGED		
376+29, RT.	LANE AHEAD 900.57	1	24"	30"	5.00						1			X																			REMOVED	NO. 4	
376+88, LT.	NO PARKING ANY TIME 900.57	1	24"	30"	5.00						1			X																			VR-020 (MODIFY)	NO. 5	
377+00, LT.	900.57	1	36"	36"	9.00						2			X																			W4-2 REMOVED		E-151
377+82, RT.	SO. BURLINGTON SHELBURNE 900.57	1	60"	7.5"	3.13						1			X																			TOWN LINE SIGN		E-124
378+19, LT.	SHELBURNE SO. BURLINGTON 900.57	1	60"	7.5"	3.13						1			X																			TOWN LINE SIGN		E-124
378+47, RT.	Ascension Lutheran 1/4 675.60	1	72"	16"				X			2			X																			SALVAGED		
	Pepsi-Cola Bottling Co. 1/4 675.60	1	72"	16"				X																									SALVAGED		
	Irish's Farm Stand 1/4	1	72"	16"				X																									SALVAGED MISSING		
378+59, LT.	900.57	1	24"	30"	5.00						1			X																			R4-7		E-144
	675.20	1	18"	18"	2.25																												OM-1		E-150
378+80, LT.	LANE ENDS 900.57	1	24"	30"	5.00						1			X																			REMOVED	NO. 4	
378+84, RT.	NO PARKING ANY TIME 900.57	1	24"	30"	5.00						1			X																			VR-020 (MODIFY)	NO. 5	
379+11, LT.	ONE WAY 900.57	1	36"	12"	3.00						1			X																			R6-1R		E-142
379+39, LT.	ONE WAY 900.57	1	36"	12"	3.00						1			X																			R6-1R		E-142
379+98, LT.	SPEED LIMIT 40	1	24"	30"	5.00						1			X																			R2-1		E-142
												FT 0	FT 0	FT 203	FT	FT	FT		FT	FT	FT	FT		FT	FT	FT	FT								
TOTALS		SF 54	SF 0	EA. 1	EA. 3							FT 203			FT					FT			EA.	FT				EA.	EA.	FT					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

AS-BUILT LEGEND

PAVEMENT \OTHER AS-BUILTS

AS-BUILT REVISIONS

NO.	DATE	DESCRIPTION
1.	6/29/06	NOTES ADDED PER ENGINEERS MARK UPS

NOTE:
1. ITEM # 675.20 ORIGINAL ENCAPSULATED SHEETING
2. ITEM # 900.57 MODIFIED TO ENCAPSULATED SHEETING BY CO# 21

4/4/03

SHELBURNE – SOUTH BURLINGTON

SURVEYED BY V.S.C. INC. DATE _____
DRAWN BY E.A.A. INC. DATE _____
TRACED BY E.A.A. INC. DATE _____

PROJECT NH-EGC-019-4(28)
SIGN SUMMARY DRAWING NO. 1
SHEET NO. 103 OF 283

C:\6330008 (US Rte 7 Shelburne Rd)\AS-BUILTS\SIGNING-STRIPING\SIGN DATA\SD-01_4.DWG, 6/30/2006 10:00:24 AM