STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD 1.7	TUBULAR STEEL ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGNS REQUIRED	REMARKS	SIGN DETAIL TRAFFIC SIGN DETAIL DWG.	STD. SHEET NUMBER
383+65.5, LT.	SHELBURNE RD 675.60	1	90"	12"	7.50																												MOUNT ON MAST ARM (CANTILEVER #3)	NO. 1	
384+27, RT.	ONLY 675.60	1	30"	36"	7.50																												MOUNT ON MAST ARM (CANTILEVER #4)	NO. 2	
	ALLEN RD 675.60	1	60"	12"	5.00																												MOUNT ON MAST ARM (CANTILEVER #4)	NO. 1	
384+35, LT.	900.57	1	24"	30"	5.00						1			X																			R4-7		E-144
	675.20	1	18"	18"	2.25																												OM-1		E-150
	LEFT TURN OR U TURN 900.57	1	24"	30"	5.00																													NO. 3	
	0070 0414 0010 900.57	1	6"	8"	0.33																												SIGN SHALL FACE SOUTHBOUND DIRECTION		E-138
384+90, RT.	NO PARKING IN BUS LANE 900.57	1	24"	30"	5.00						1			X																			VR-020 (MODIFY)	NO. 5	
	CCTA BUS STOP 675.60	1																															PROVIDED BY OTHERS		
385+01, LT.	STOP 675.20	1	30"	30"	6.25						1			X																			R1-1		E-143
	900.57	1	24"	24"	4.00																												R3-2		E-143
385+12, LT.	ONE WAY 900.57	1	36"	12"	3.00						1			X																			R6-1R		E-142
385+45, LT.	PVT NESTI DR / PVT NESTI DR 900.57	1	36"	9"	2.25						1			X																			RURAL TOP MOUNTED - TEXT ON BOTH SIDES	NO. 1	E-123
385+67, RT.	RIGHT LANE ONLY 900.57	1	24"	30"	5.00						1			X																				NO. 4	
386+93, LT.	TRUCK U-TURN 1/2 MILE AHEAD 900.57	1	24"	30"	5.00						1			X																				NO. 3	
386+97, RT.	SPEED LIMIT 40 900.57	1	24"	30"	5.00						1			X																			R2-1		E-142
												FT 0	FT 0	FT 102	FT	FT	FT		FT	FT	FT	FT		FT	FT	FT	FT								
	TOTALS				SF 68	SF 0	EA. 0	EA. 0				FT 102			FT					FT			EA.	FT				EA.	EA.	FT					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

AS-BUILT LEGEND
PAVEMENT \OTHER AS-BUILTS

AS-BUILT REVISIONS

NO.	DATE	DESCRIPTION
1.	6/29/06	NOTES ADDED PER ENGINEERS MARK UPS

NOTE:
1. ITEM # 675.20 ORIGINAL ENCAPSULATED SHEETING
2. ITEM # 900.57 MODIFIED TO ENCAPSULATED SHEETING BY CO# 21

4/4/03

SHELBURNE - SOUTH BURLINGTON

SURVEYED BY V.S.C. INC. DATE
DRAWN BY E.A.A. INC. DATE
TRACED BY E.A.A. INC. DATE

PROJECT NH-EGC-019-4(28)
SIGN SUMMARY DRAWING NO. 3
SHEET NO. 105 OF 283

C:\6330008 (US Rte 7 Shelburne Rd)\AS-BUILTS\SIGNING-STRIPING\SIGN DATA\SD-03_4.DWG, 6/30/2006 10:01:19 AM