# STATE OF VERMONT
# AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET

| MILE MARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | WIDTH (in) | HEIGHT (in) | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | SALVAGE | NO. OF POSTS | NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12 | 2.0 | 3.0 | SQUARE STEEL (in) 1.75 lb/ft 1.88 | 2.0 lb/ft 2.16 | 2.5 lb/ft 3.35 | ANCHOR | SLEEVE | TUBULAR ALUMINUM ø (in) 3.0 lb/ft 1.3 | 4.0 lb/ft 1.7 | 4.0 MOD 1.7 | TUBULAR STEEL ø (in) FOUND-ATION | 3.0 lb/ft 7.6 | 3.5 lb/ft 9.0 | 4.0 lb/ft 10.8 | 5.0 lb/ft 14.6 | W-SHAPE STEEL FTG. SIZE 24" | 30" | WEIGHT | POST SIZE | REQUIRED SIGNS | REMARKS | SIGN DETAIL: TRAFFIC SIGN DETAIL DWG. | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 393+72, RT. | SPEED LIMIT 40 900.51 | 1 | 24" | 30" | 5.00 | | | | | | 1 | | | X | | | | | | | | | | | | | | | | | | | | R2-1 | | E-142 |
| 394+00, LT. | Champ Car Care Ctr. next left 675.60 | 1 | 72" | 16" | | | | X | | | 2 | | | X | | | | | | | | | | | | | | | | | | | | SALVAGED | | |
| 394+32, LT. | ONE WAY 900.57 | 1 | 36" | 12" | 3.00 | | | | | | 1 | | | X | | | | | | | | | | | | | | | | | | | | R6-1R | | E-142 |
| 396+12, LT. | ONE WAY 900.57 | 1 | 36" | 12" | 3.00 | | | | | | 1 | | | X | | | | | | | | | | | | | | | | | | | | R6-1R | | E-142 |
| 396+33, LT. | TRUCK U-TURN 2½ MILES AHEAD 900.57 | 1 | 24" | 30" | 5.00 | | | | | | 1 | | | X | | | | | | | | | | | | | | | | | | | | | NO. 3 | |
| 398+90, LT. | 0070 0414 0040 900.57 | 1 | 6" | 8" | 0.33 | | | | | | 1 | | | X | | | | | | | | | | | | | | | | | | | | | | E-138 |
| 399+33, LT. | ONE WAY 900.57 | 1 | 36" | 12" | 3.00 | | | | | | 1 | | | X | | | | | | | | | | | | | | | | | | | | R6-1R | | E-142 |
| 400+48, LT. | TRUCK U-TURN 1/4 MILE AHEAD 900.57 | 1 | 24" | 30" | 5.00 | | | | | | 1 | | | X | | | | | | | | | | | | | | | | | | | | | NO. 3 | |
| 402+47, LT. | SPEED LIMIT 40 900.57 | 1 | 24" | 30" | 5.00 | | | | | | 1 | | | X | | | | | | | | | | | | | | | | | | | | R2-1 | | E-142 |
| 402+74, LT. | ONE WAY 900.57 | 1 | 36" | 12" | 3.00 | | | | | | 1 | | | X | | | | | | | | | | | | | | | | | | | | R6-1R | | E-142 |
| 403+90, LT. | RIGHT LANE ONLY 900.57 | 1 | 24" | 30" | 5.00 | | | | | | 1 | | | X | | | | | | | | | | | | | | | | | | | | | NO. 4 | |
| 404+46, LT. | NO PARKING IN BUS LANE 900.57 | 1 | 24" | 30" | 5.00 | | | | | | 1 | | | X | | | | | | | | | | | | | | | | | | | | VR-020 (MODIFY) | NO. 5 | |
| | CCTA BUS STOP 675.60 | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | PROVIDED BY OTHERS | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | FT 0 | FT 0 | FT 159 | FT | FT | FT | | FT | FT | FT | FT | | FT | FT | FT | FT | | | | | | | | |
| | TOTALS | | | | SF 42 | SF 0 | EA. 0 | EA. 1 | | | | FT 159 | | | FT | | | | | FT | | | EA. | FT | | | | EA. | EA. | FT | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

**AS-BUILT LEGEND**

PAVEMENT \OTHER AS-BUILTS

**AS-BUILT REVISIONS**

| NO. | DATE | DESCRIPTION |
|---|---|---|
| 1. | 6/29/06 | NOTES ADDED PER ENGINEERS MARK UPS |
| | | |

**NOTE:**
1. ITEM # 675.20 ORIGINAL ENCAPSULATED SHEETING
2. ITEM # 900.57 MODIFIED TO ENCAPSULATED SHEETING BY CO# 21

4/4/03

SHELBURNE – SOUTH BURLINGTON

SURVEYED BY V.S.C. INC. DATE _____
DRAWN BY E.A.A. INC. DATE _____
TRACED BY E.A.A. INC. DATE _____

PROJECT NH-EGC-019-4(28)
SIGN SUMMARY DRAWING NO. 6
SHEET NO. 108 OF 283

C:\6330008 (US Rte 7 Shelburne Rd)\AS-BUILTS\SIGNING-STRIPING\SIGN DATA\SD-06_4.DWG, 6/30/2006 10:02:31 AM