QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

		TOWN WATER NON-PART.	TOWN WATER PART.	TOWN SEWER NON-PART.	TOWN SEWER PART.	E & C	EROSION CONTROL	ROADWAY PARTIC.	TRAINING	STRUCTURES	LANDSCAPING	QUANTITY GRAND TOTAL	UNIT	DESCRIPTION OF ITEMS	ITEM NUMBER	ROUNDING
														BEGIN OPTIONAL BID ITEMS		
														OPTION FOR 12" PIPE		
								50				50	LF	12" CAAP .060 (2-2/3x1/2)	601.0205	32
								50				50	LF	12" PCCSP .064 (2-2/3x1/2)	601.0405	32
								50				50	LF	12" RCP, CLASS III	601.0805	32
								50				50	LF	12" CPEP, (SL)	601.2605	32
														OPTION FOR 18" PIPE		
								15,750				15,750	LF	18" CAAP 0.060 (2-2/3X1/2)	601.0215	255
								15,750				15,750	LF	18" PCCSP 0.064 (2-2/3X1/2)	601.0415	255
								15,750				15,750	LF	18" RCP, CLASS III	601.0815	255
								15,750				15,750	LF	18" CPEP, (SL)	601.2615	255
														OPTION FOR 24" PIPE		
								3,000				3,000	LF	24" CAAP 0.060 (2-2/3X1/2)	601.0225	155
								3,000				3,000	LF	24" PCCSP 0.064 (2-2/3X1/2)	601.0425	155
								3,000				3,000	LF	24" RCP, CLASS III	601.0825	155
								3,000				3,000	LF	24" CPEP, (SL)	601.2620	155
														OPTION FOR 30" PIPE		
								2,400				2,400	LF	30" CAAP 0.075 (2-2/3X1/2)	601.0236	158
								2,400				2,400	LF	30" PCCSP 0.079 (2-2/3X1/2)	601.0436	158
								2,400				2,400	LF	30" RCP, CLASS III	601.0836	158
								2,400				2,400	LF	30" CPEP, (SL)	601.2625	158
														OPTION FOR 18" END SECTIONS		
								14				14	EA	18" CSPES 0.064 (2-2/3X1/2)	601.6015	–
								14				14	EA	18" CAAPES 0.060 (2-2/3X1/2)	601.6215	–
								14				14	EA	18" RCPES CLASS III	601.6815	–
								14				14	EA	18" CPEPES	601.7015	–
														OPTION FOR 24" END SECTIONS		
								5				5	EA	24" CSPES 0.064 (2-2/3X1/2)	601.6025	–
								5				5	EA	24" CAAPES 0.060 (2-2/3X1/2)	601.6225	–
								5				5	EA	24" RCPES CLASS III	601.6825	–
								5				5	EA	24" CPEPES	601.7020	–
														OPTION FOR 30" END SECTIONS		
								3				3	EA	30" CSPES 0.079 (2-2/3X1/2)	601.6036	–
								3				3	EA	30" CAAPES 0.075 (2-2/3X1/2)	601.6236	–
								3				3	EA	30" RCPES CLASS III	601.6835	–
								3				3	EA	30" CPEPES	601.7025	–
														END OPTION BID ITEMS		
								90				90	EA	PRECAST REINFORCED CONC. CATCH BASIN WITH C.I. GRATE (48")	604.20	–
								25				25	EA	PRECAST REINFORCED CONC. CATCH BASIN WITH C.I. GRATE (72")	604.20	–
								3				3	EA	PRECAST REINFORCED CONC. MANHOLE WITH C.I. COVER (48")	604.21	–
								2				2	EA	PRECAST REINFORCED CONC. MANHOLE WITH C.I. COVER (72")	604.21	–
				34	8							42	EA	SANITARY SEWER MANHOLE (48")	604.22	–
								29				29	EA	PRC CURB DROP INLET WTH C.I. GRATE	604.30	–

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	DESCRIPTION OF ITEMS

TYPE OF CONSTRUCTION

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS 74'-0" C – C	TAPER						EQUATIONS +	EQUATIONS –
TOTALS		12,260'								

STATIONS		FEET	MILES	REMARKS
TOTALS		16,383	3.10	

PROJECT NAME: U.S. ROUTE 7: SHELBURNE ROAD (F.A.P.)

PROJECT NUMBER: NH-EGC-019-4(27) 4/13/04

QUANTITY DRAWING NO. 2

SHEET 20 OF 537 SHEETS