QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

		TOWN WATER NON-PART.	TOWN WATER PART.	TOWN SEWER NON-PART.	TOWN SEWER PART.	E & C	EROSION CONTROL	ROADWAY PARTIC.	TRAINING	STRUCTURES	LANDSCAPING	QUANTITY GRAND TOTAL	UNIT	DESCRIPTION OF ITEMS	ITEM NUMBER	ROUNDING
								2				2	EA	CHANGING ELEV OF DROP INLETS, CATCH BASINS OR MANHOLES	604.40	–
				5								5	EA	CHANGING ELEVATION OF SEWER MANHOLE	604.42	–
					1							1	EA	REHABILITATION OF SEWER MANHOLES (MOD 1)	604.43	–
				4				2				6	EA	REHABILITATION OF SEWER MANHOLES (MOD 2)	604.43	–
								23,500				23,500	LF	6" UNDERDRAIN	605.10	261
								115				115	HR	BULLDOZER RENTAL, TYPE I	608.10	EST
								115				115	HR	POWER GRADER RENTAL	608.15	EST
							50	65				115	HR	ALL-PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
							250	250				500	HR	POWER BROOM RENTAL	608.30	EST
							500	500				1,000	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
							500	500				1,000	HR	TRUCK RENTAL	608.37	EST
							50	65				115	HR	LOADER RENTAL, TYPE I	608.40	EST
							11,000	11,000				22,000	MGAL	DUST CONTROL WITH WATER	609.10	472
											250	250	MGAL	DUST CONTROL WITH WATER (MOD)	609.10	EST.
							150	300				450	TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	61
							100	700				800	CY	STONE FILL, TYPE I	613.10	73
							80					80	CY	STONE FILL, TYPE I (MOD) (CHECK DAM)	613.10	8
							180	80		1,040		1,300	CY	STONE FILL, TYPE II	613.11	109
								21,000				21,000	LF	GRANITE SLOPE EDGING	616.20	33
								24,000				24,000	LF	CAST IN PLACE CONCRETE CURB, TYPE B	616.28	538
								10				10	TON	BITUMINOUS CONCRETE CURB, TYPE A	616.30	1
								500				500	TON	BITUMINOUS CONCRETE CURB, TYPE A (MOD)	616.30	18
								6				6	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	1
								44				44	EA	RELOCATE MAIL BOX, SINGLE SUPPORT	617.10	–
								14				14	EA	RELOCATE MAIL BOX, MULTIPLE SUPPORT	617.12	–
								13,500				13,500	SY	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	618.10	119
								1,500				1,500	SY	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	618.11	189
								600				600	TON	BITUMINOUS CONCRETE SIDEWALK (MOD.)	618.15	26
								100				100	SY	DETECTABLE WARNING SURFACES	618.30	5
										150		150	LF	CHAIN LINK FENCE, 4 FEET (MOD)	620.11	15
								2,000				2,000	LF	REMOVE AND RESETTING FENCE	620.50	121
								500				500	LF	REMOVAL OF EXISTING FENCE	620.55	15
								14,500				14,500	LF	SNOW FENCE	620.70	385
								500				500	LF	SNOW FENCE (MOD)	620.70	EST
								200				200	LF	HEAVY DUTY STEEL BEAM GUARD RAIL	621.21	50
								3				3	EA	MODIFIED ECCENTRIC LOADER TERMINAL	621.54	–
								4				4	EA	ENERGY ABSORPTION ATTENUATOR	621.56	–
								1				1	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	–
								600				600	LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	93
								52				52	EA	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	–

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	DESCRIPTION OF ITEMS

TYPE OF CONSTRUCTION

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS 74'-0" C – C	TAPER						EQUATIONS +	EQUATIONS –
TOTALS		12,260'								

STATIONS	FEET	MILES	REMARKS
TOTALS	16,383	3.10	

PROJECT NAME: U.S. ROUTE 7: SHELBURNE ROAD (F.A.P.)

PROJECT NUMBER: NH-EGC-019-4(27) 4/13/04

QUANTITY DRAWING NO. 3

SHEET 21 OF 537 SHEETS