QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

DETOUR	TOWN WATER NON-PART.	TOWN WATER PART.	TOWN SEWER NON-PART.	TOWN SEWER PART.	E & C	EROSION CONTROL	ROADWAY PARTIC.	TRAINING	STRUCTURES	LANDSCAPING	QUANTITY GRAND TOTAL	UNIT	DESCRIPTION OF ITEMS	ITEM NUMBER	ROUNDING
					1						1	LS	TESTING EQUIPMENT – BITUMINOUS	631.17	–
					1						1	LU	FIELD OFFICE – TELEPHONE (NABI)	631.25	–
								3,120			3,120	HR	EMPLOYEE TRAINEESHIP	634.10	–
							1				1	LS	MOBILIZATION (MOD)	635.10	–
							1				1	LS	TRAFFIC CONTROL (MOD)	641.10	–
1											1	LS	TRAFFIC CONTROL (BAY RD DETOUR)	641.10	–
							5				5	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	–
							5				5	EA	PORTABLE ARROW BOARD	641.16	–
							17,000				17,000	LF	4" WHITE LINE	646.20	527
							31,000				31,000	LF	4" YELLOW LINE	646.21	423
							15,500				15,500	LF	DURABLE 4" WHITE LINE (THERMOPLASTIC)	646.40	525
							28,000				28,000	LF	DURABLE 4" YELLOW LINE (THERMOPLASTIC)	646.41	203
							22,000				22,000	LF	DURABLE 6" WHITE LINE (THERMOPLASTIC)	646.414	176
							850				850	LF	DURABLE 8" WHITE LINE (THERMOPLASTIC)	646.42	62
							1,000				1,000	LF	DURABLE 24" STOP BAR (TAPE, TYPE I)	646.46	63
							452				452	EA	DURABLE ARROW OR SYMBOL (TAPE, TYPE I)	646.50	–
							2,000				2,000	LF	DURABLE CROSSWALK W/ DIAGONAL LINES (TAPE, TYPE I)	646.51	100
							81,000				81,000	LF	TEMPORARY 4" WHITE LINE	646.60	680
							5,000				5,000	LF	TEMPORARY 4" WHITE LINE (TAPE, TYPE I)	646.60	230
							16,000				16,000	LF	TEMPORARY 4" WHITE LINE (TAPE, TYPE II)	646.60	690
							67,000				67,000	LF	TEMPORARY 4" YELLOW LINE	646.61	776
							5,000				5,000	LF	TEMPORARY 4" YELLOW LINE (TAPE, TYPE I)	646.61	444
							12,000				12,000	LF	TEMPORARY 4" YELLOW LINE (TAPE, TYPE II)	646.61	444
							600				600	LF	TEMPORARY 8" YELLOW LINE (TAPE, TYPE II)	646.63	50
							2,300				2,300	LF	TEMPORARY 24" STOP BAR	646.66	60
							300				300	EA	TEMPORARY LETTER OR SYMBOL	646.70	EST
							1,700				1,700	LF	TEMPORARY CROSSWALK W/ DIAGONAL LINES	646.71	EST
							500				500	EA	LINE STRIPING TARGETS	646.76	EST
							13,500				13,500	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	167
							13,500				13,500	SF	BLACK PAVEMENT MARKING MASKING TAPE	646.86	167
							11,300				***11,300***	SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	571
							12,700				***12,700***	***SY***	***GEOTEXTILE FOR ROADBED SEPERATOR (MOD)***	***649.11***	
								500			***500***	SY	GEOTEXTILE UNDER STONE FILL	649.31	***500***
								2500			***2500***	***SY***	***GEOTEXTILE UNDER STONE FILL (MOD I)***	***649.31***	***30***
							1,200				1,200	SY	GEOTEXTILE UNDER STONE FILL***(MOD II)***(GEOWEB)	649.31	33
						1000					***1000***	SY	GEOTEXTILE FABRIC FOR SILT FENCE	649.51	***1000***
						7500					***7500***	***SY***	***GEOTEXTILE FABRIC FOR SILT FENCE (MOD)***	***649.51***	***132***
							1,400			900	2,300	LB	SEED	651.15	90
							6,600			900	7,500	LB	FERTILZER	651.18	51
										1,300	1,300	LB	FERTILIZER (MOD) (MYCORRHIZAL)	651.18	80
							26			10	36	TON	AGRICULTURAL LIMESTONE	651.20	–

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	DESCRIPTION OF ITEMS

TYPE OF CONSTRUCTION

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS 74'-0" C – C	TAPER						EQUATIONS +	EQUATIONS –
TOTALS		12,260'								

STATIONS		FEET	MILES	REMARKS
TOTALS		16,383	3.10	

PROJECT NAME: U.S. ROUTE 7: SHELBURNE ROAD (F.A.P.)

PROJECT NUMBER: NH-EGC-019-4(27)

4/13/04

QUANTITY DRAWING NO. 5

SHEET 23 OF 537 SHEETS