QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

		TOWN WATER NON-PART.	TOWN WATER PART.	TOWN SEWER NON-PART.	TOWN SEWER PART.	E & C	EROSION CONTROL	ROADWAY PARTIC.	TRAINING	STRUCTURES	LANDSCAPING	QUANTITY GRAND TOTAL	UNIT	DESCRIPTION OF ITEMS	ITEM NUMBER	ROUNDING
								26			10	36	TON	HAY MULCH (MOD) (STRAW MULCH)	651.25	–
							20					20	EA	HAY BALES FOR EROSION CONTROL (MOD)	651.26	EST
											90	90	CY	CEDAR BARK MULCH	651.27	–
								7,100			4,100	11,200	CY	TOPSOIL	651.35	126
											700	700	CY	TOPSOIL (MOD) (COMPOST)	651.35	60
										1,600		1,600	SY	GRUBBING MATERIAL	651.40	90
							1					1	LS	EROSION & SEDIMENT CONTROL PLAN	652.10	–
							2,200					2,200	HR	MONITORING EROSION & SEDIMENT CONTROL PLAN	652.20	EST
							1					1	LU	FIELD MAINTENANCE OF EROSION & SEDIMENT CONTROL PLAN (NABI)	652.30	–
							1000					***1000***	SY	EROSION MATTING (SLOPES)	654.10	***1000***
							6000					***6000***	***SY***	***EROSION MATTING (MOD) (SLOPES)***	***654.10***	***172***
							1000					***1000***	SY	EROSION MATTING (DITCHES)	654.10	***1000***
							7000					***7000***	***SY***	***EROSION MATTING (MOD) (DITCHES)***	***654.10***	***198***
											116	116	EA	EVERGREEN SHRUBS (HETZ BLUE JUNIPER) (18")	656.25	–
											44	44	EA	DECIDUOUS TREES (TRAZAM SERVICEBERRY) (1 3/4" – 2" CAL.)	656.31	–
											51	51	EA	DECIDUOUS TREES (CUMULUS SERVICEBERRY) (1 3/4" – 2" CAL.)	656.31	–
											63	63	EA	DECIDUOUS TREES (SNOWCLOUD SERVICEBERRY) (1 3/4" – 2" CAL.)	656.31	–
											14	14	EA	DECIDUOUS TREES (TATARIAN MAPLE) (1 3/4" – 2" CAL.)	656.31	–
											6	6	EA	DECIDUOUS TREES (AMUR MAACKIE) (1 3/4" – 2" CAL.)	656.31	–
											42	42	EA	DECIDUOUS TREES (COLUMNAR SIBERIAN CRAB) (1 3/4" – 2" CAL.)	656.31	–
											31	31	EA	DECIDUOUS TREES (WALTERS SIBERIAN CRAB) (1 3/4" – 2" CAL.)	656.31	–
											41	41	EA	DECIDUOUS TREES (HARVEST GOLD CRABAPPLE) (1 3/4" – 2" CAL.)	656.31	–
											71	71	EA	DECIDUOUS TREES (SPRING SNOW CRABAPPLE) (1 3/4" – 2" CAL.)	656.31	–
											31	31	EA	DECIDUOUS TREES (IVORY SILK TREE LILAC) (1 3/4" – 2" CAL.)	656.31	–
											44	44	EA	DECIDUOUS TREES (CLEVELAND SELECT PEAR) (2" – 2 1/2" CAL.)	656.33	–
											18	18	EA	DECIDUOUS TREES (AUTUM BLAZE MAPLE) (2 1/2" – 3" CAL.)	656.34	–
											9	9	EA	DECIDUOUS TREES (NORTHFIRE RED MAPLE) (2 1/2" – 3" CAL.)	656.34	–
											8	8	EA	DECIDUOUS TREES (HACKBERRY) (2 1/2" – 3" CAL.)	656.34	–
											3	3	EA	DECIDUOUS TREES (SHADEMASTER HONEYLOCUST) (2 1/2" – 3" CAL.)	656.34	–
											12	12	EA	DECIDUOUS TREES (RED OAK) (2 1/2" – 3" CAL.)	656.34	–
											4	4	EA	DECIDUOUS TREES (BURR OAK) (2 1/2" – 3" CAL.)	656.34	–
											6	6	EA	DECIDUOUS TREES (ACCOLADE ELM) (2 1/2" – 3" CAL.)	656.34	–
											28	28	EA	DECIDUOUS TREES (GREEN VASE ZELKOVA) (2 1/2" – 3" CAL.)	656.34	–
											69	69	EA	DECIDUOUS SHRUBS (RED CHOKEBERRY) (36")	656.35	–
											175	175	EA	DECIDUOUS SHRUBS (RUGOSA ROSE) (18")	656.35	–
											600	600	EA	GROUND COVERS AND VINES (HARDSTEM BULRUSH) (2")	656.40	–
											3,300	3,300	EA	GROUND COVERS AND VINES (THREESQUARE) (2")	656.40	–
											3,300	3,300	EA	GROUND COVERS AND VINES (WOOLGRASS) (2")	656.40	–
											2,200	2,200	EA	GROUND COVERS AND VINES (SOFTSTEM BULRUSH) (2")	656.40	–

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	DESCRIPTION OF ITEMS

TYPE OF CONSTRUCTION

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS 74'-0" C – C	TAPER						EQUATIONS +	EQUATIONS –
TOTALS		12,260'								

STATIONS		FEET	MILES	REMARKS
TOTALS		16,383	3.10	

PROJECT NAME: U.S. ROUTE 7: SHELBURNE ROAD (F.A.P.)

PROJECT NUMBER: NH-EGC-019-4(27) 4/13/04

QUANTITY DRAWING NO. 6

SHEET 24 OF 537 SHEETS