



**CURVE NO. C172  
JUNIPER RIDGE**  
 P.I. STA. 253+61.58 BK.=  
 STA. 253+61.25 AHD.  
 $\Delta = 13^\circ 19' 07''$   
 $D = 19' 05' 55''$   
 $R = 300.00'$   
 $L = 69.74'$   
 $T = 35.03'$   
 $E = 2.04'$   
 P.C. STA. 253+26.55  
 P.T. STA. 253+96.28

DEMOLITION & DISPOSAL OF:  
D129 @ JUNIPER 253+15, LT (SIGN)

CONSTRUCT DRIVE  
JUNIPER 252+87 LT - 44'  
JUNIPER 253+21 RT - 9'

**NOTES:**  
 1. UNDERGROUND AND AERIAL UTILITY LOCATIONS ARE PLOTTED BASED ON THE BEST AVAILABLE INFORMATION. LOCATIONS SHOULD BE VERIFIED BY THE CONTRACTOR BEFORE WORK.  
 2. SEE PLAN NOTES DRAWING NO. 1 FOR PLAN NOTES AND GENERAL NOTES.

**RECORD DRAWING REVISIONS**

| NO. | DATE    | DESCRIPTION                       |
|-----|---------|-----------------------------------|
| 1.  | 7/24/09 | FIELD MARK UPS ADDED TO THE PLANS |

SHELBURNE

SURVEYED BY V.S.C. INC. DATE \_\_\_\_\_  
 DRAWN BY E.A.A. INC. DATE \_\_\_\_\_  
 TRACED BY E.A.A. INC. DATE \_\_\_\_\_

PROJECT NH-EGC-019-4(27)  
 PLAN DRAWING NO. 24  
 SHEET NO. 127 OF 537

DATUM  
 VERTICAL NGVD 1929  
 HORIZONTAL NAD 1927

FOR PROFILE SEE PROFILE DRAWING NO. 25 7/20/04

