STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL ø (in) FOUND-ATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL TRAFFIC SIGN DETAIL DWG.	STD. SHEET NUMBER
	0070 0414 0380	1	6"	8"	0.33																														E-138
323+94, LT.		1	18"	18"	2.25						1																					OM-1		E-150
324+16, RT.	NO PARKING IN BUS LANE	1	24"	30"	5.00						1			X																			NO. 5	
	CCTA BUS STOP	1																														PROVIDED BY OTHERS		
324+93, RT.	RIGHT LANE ONLY	1	24"	30"	5.00						1			X																		R3-17		E-143B
324+93, LT.	11'-0"	1	36"	36"	9.00						2			X																		W12-2		E-155
		1	21"	15"	2.19																											M6-2R		E-136A
325+15, LT.	BAY RD	1	60"	10"	4.16						2			X																			NO. 3	
325+76, RT.	ONE WAY	1	36"	12"	3.00						1			X																		R6-1R		E-142
326+56, RT.	SPEED LIMIT 40	1	24"	30"	5.00						1			X																		R2-1		E-142
328+21, RT.	ONE WAY	1	36"	12"	3.00						1			X																		R6-1R		E-142
329+16, LT.	ONE WAY	1	36"	12"	3.00						1			X																		W6-1R		E-142
329+40, CL	TRUCK U-TURN 1 3/4 MILES AHEAD	1	24"	30"	5.00						1			X																			NO. 4	
	TRUCK U-TURN 1 MILE AHEAD	1	24"	30"	5.00																												NO. 4	
												FT 0	FT 0	FT 138	FT	FT	FT		FT	FT	FT	FT		FT	FT	FT	FT								
TOTALS					SF 52	SF 0	EA. 0	EA. 0				FT 138			FT					FT			EA.	FT				EA.	EA.	FT				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

RECORD DRAWING REVISIONS

NO.	DATE	DESCRIPTION
1.	7/24/09	FIELD MARK UPS ADDED TO THE PLANS

7/20/04

SHELBURNE
SURVEYED BY V.S.C. INC. DATE
DRAWN BY E.A.A. INC. DATE
TRACED BY E.A.A. INC. DATE

PROJECT NH-EGC-019-4(27)
SIGN SUMMARY DRAWING NO. 11
SHEET NO. 191 OF 537