STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	VERTICAL CLEARANCE REQUIRED	REMARKS	SIGN DETAIL TRAFFIC SIGN DETAIL DWG.	STD. SHEET NUMBER
JUNIPER RIDGE 250+43, RT.	SHELBURNE RD	1	42"	9"	2.63						1			X																			RURAL TOP MOUNTED – TEXT ON BOTH SIDES	NO. 1	E-123
	JUNIPER RIDGE	1	42"	9"	2.63																												RURAL TOP-MOUNTED – TEXT ON BOTH SIDES	NO. 1	E-123
JUNIPER RIDGE 250+57, LT.	STOP	1	30"	30"	6.25						1			X																			R1-1		E-143
JUNIPER RIDGE 250+82, RT.	LEGAL LOAD LIMIT 24 000 POUNDS	1	24"	24"	4.00						1			X																			VR-017		E-141
		1	X	X			X				1			X																			SALVAGED		
JUNIPER RIDGE 251+70, RT.	SPEED LIMIT 25	1	24"	30"	5.00						1			X																			R2-1		E-142
JUNIPER RIDGE 253+37, LT.		1	36"	36"	9.00						2			X																			W3-1A		E-150
JUNIPER RIDGE 253+68, LT.	STOP	1	30"	30"	6.25						1			X																			R1-1		E-143
PRIVATE ROAD 260+50, RT.	SHELBURNE RD	1	42"	9"	2.63						1			X																			RURAL TOP MOUNTED – TEXT ON BOTH SIDES	NO. 1	E-123
	CLEARWATER RD	1	42"	9"	2.63																												RURAL TOP-MOUNTED – TEXT ON BOTH SIDES	NO. 1	E-123
PRIVATE ROAD 260+57, LT.	SHELBURNE RD	1	42"	9"	2.63						1			X																			RURAL TOP MOUNTED – TEXT ON BOTH SIDES	NO. 1	E-123
	PALMER CT	1	42"	9"	2.63																												RURAL TOP-MOUNTED – TEXT ON BOTH SIDES	NO. 1	E-123
PRIVATE ROAD 260+61, LT.	STOP	1	30"	30"	6.25						1			X																			R1-1		E-142
PRIVATE ROAD 261+13, RT.	NO OUTLET	1	30"	30"	6.25						2			X																				NO. 3	
												FT 0	FT 0	FT 192	FT	FT	FT		FT	FT	FT	FT		FT	FT	FT	FT								
TOTALS			SF 58	SF 0	EA. 1	EA. 0						FT 192			FT					FT			EA.	FT				EA.	EA.	FT					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

4/13/04

SHELBURNE
SURVEYED BY V.S.C. INC. DATE
DRAWN BY E.A.A. INC. DATE
TRACED BY E.A.A. INC. DATE

PROJECT NH-EGC-019-4(27)
SIGN SUMMARY DRAWING NO. 27
SHEET NO. 207 OF 537