STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
											OPTION ITEMS																									
U.S. ROUTE 4 0+021.0, RT	STATE LAW STOP FOR SCHOOL BUS FLASHING RED LIGHTS	1	600	750	0.45						1			X		X																			E-144M
0+041.0, RT	Welcome To VERMONT THE GREEN MOUNTAIN STATE	1	1500	1200	1.80						2						X																THESE POSTS ARE NOT TO BE OPTIONED.	47	
0+070.0, RT	EAST / EAST	1 1	750 750	375 375	0.28 0.28						2												2	X								X		E-136AM E-136BM
	4 / VERMONT 4A	1 1	900 900	900 900	0.81 0.81																													E-136AM E-136BM
		1 1	525 525	375 375	0.20 0.20																													E-136AM E-136BM
0+097.0, RT	ONLY	1	750	750	0.56						1			X		X																			E-145AM
0+104.0, LT	WHITEHALL NY 5	1	1800	250	0.45						2			X		X																		60	
0+167.0, LT		1	1200	1200	1.44						2						X																THESE POSTS ARE NOT TO BE OPTIONED.		E-151M
0+198.0, RT		1	450	450	0.20						1	X			X																			E-150M
0+198.0, RT	YIELD 1500X1500X1500	1			1.01						2			X		X																			E-146M
211 0+~~200.0~~, RT	WELCOME CENTER WEIGH STATION	1	2550	3450		8.80					2												2				X						460mm DIA. CONCRETE BASE 127mm DIA. POST (2 EA.)	48	
213 0+~~212.0~~, RT	WELCOME CENTER WEIGH STATION	1	2550	3750		9.56					2												2				X						460mm DIA. CONCRETE BASE 127mm DIA. POST (2 EA.)	48	
0+212.0, LT	STOP / DO NOT ENTER	1 1	1200 1200	1200 1200	1.44 1.44						2						X						2	X									THESE POSTS ARE NOT TO BE OPTIONED. BACK-TO-BACK		E-143M E-143M
	ONE WAY / ONE WAY	1 1	900 900	300 300	0.27 0.27																												BACK-TO-BACK		E-142M E-142M
0+222.0, RT	STOP	1 1	1200 1200	1500 1200	1.80 1.44						2						X						2	X									THESE POSTS ARE NOT TO BE OPTIONED. BACK-TO-BACK		E-144M E-143M
		1 1	450 450	450 450	0.20 0.20																														E-150M
											m 4.6	m	m 27.6	m 4.6	m 27.6	m 0.0/36.8		EA	kg	kg	kg		kg 271.5	kg	kg	kg 466.6							
TOTALS		m^2 15.55	m^2 18.36	EA	m^2		m 32.2		m 32.2/36.8			kg			EA 10		kg 738.1				EA	EA	kg										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
FAIR HAVEN - RUTLAND	NH 9727(I)S

DESIGN FILE NAME: /pave/96bl54/pbl54.dgn
IPARM FILE NAME: pbl54t01.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 8/98
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 76 OF 119