STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
U.S. ROUTE 4 1+400.0, LT	REDUCED SPEED AHEAD	1	1200	1500	1.80						2						X																	THESE POSTS ARE NOT TO BE OPTIONED.		E-142M
1+571.0, LT	WEIGH STATION NEXT RIGHT / CLOSED	1	2850	2400		6.84					2																	2		129.6	W150X13.5		600mm DIA. CONCRETE BASE (2 EA.)	69	
1+609.3, LT	MILE 1	1	300	600	0.18						1		X			X																			E-139M
1+670.0, LT	SPEED LIMIT 65	1	1200	1500	1.80						2												2	X									460mm DIA. CONCRETE BASE 127mm DIA. POST (2 EA.)		E-142M
	MINIMUM 40	1	1200	1200	1.44																														E-142M
739 1+~~897.0~~, LT	WELCOME CENTER / WEIGH STATION 1 MILE	1	4350	2250		9.79					3																	3		232.2	W150X13.5		600mm DIA. CONCRETE BASE (2 EA.)	49	
1+951.0, RT		1	1200	1200	1.44						2						X																	THESE POSTS ARE NOT TO BE OPTIONED.		E-143M
1+975.0, LT	WEST	1	750	375	0.28						1						X																	THIS POST IS NOT TO BE OPTIONED.		E-136AM
	4	1	900	900	0.81																														E-136AM
2+361.0, RT	ONE WAY	1	900	300	0.27						1			X		X																			E-142M
2+646.0, LT		1	1200	1200	1.44						2			X			X																			E-150M
2+753.0, LT	BR 5-W US4	1	150	200	0.03						1	X			X																					E-134M
940 2+~~955.0~~, LT	EXIT 2	1	1800	1500		2.70					2												2	X										460mm DIA. CONCRETE BASE 127mm DIA. POST (2 EA.)		E-131M
											m 4.6	m 4.6	m 13.8	m 4.6	m 9.2	m 9.2/ 23.0		EA	kg	kg	kg		kg 213.6	kg	kg	kg							
TOTALS			m^2 9.49	m^2 19.33	EA	m^2					m 23.0			m 23.0/23.0			kg	EA 4	kg 213.6			EA 5	EA	kg 361.8							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: FAIR HAVEN - RUTLAND
PROJECT NO.: NH 9727(I)S

DESIGN FILE NAME: /pave/96bl54/pbl54.dgn
IPARM FILE NAME: pbl54t03.I
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 8/98
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 78 OF 119