STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
U.S. ROUTE 4 6+893.0, RT		1	1200	1200	1.44						2						X																	THESE POSTS ARE NOT TO BE OPTIONED.		E-143M
6+954.0, LT	BRIDGES FREEZE BEFORE ROAD	1	~~1200~~ 900	~~1200~~ 900	~~1.44~~ 0.81						2						X																	THESE POSTS ARE NOT TO BE OPTIONED.		E-150M
~~7+260.0,~~ 7+304.8 LT	Fair Haven NEXT 2 EXITS	1	3000	1200		3.60					2										X															53	
7+642.0, LT	Fair Haven 3 Whitehall NY 11	1	3150	900		2.84					2												2	X										18" FNDN 3' DIA (2 EA.)	53	
~~8+042.5~~ 7+912.0, LT	SPEED LIMIT 65	1	1200	1500	1.80						2												2	X										18" FNDN 3' DIA (2 EA.)		E-142M
	MINIMUM 40	1	1200	1200	1.44																															E-142M
8+046.7, LT	MILE 5	1	300	600	0.18						1		X			X																				E-139M
8+177.0, RT		1	1200	1200	1.44						2						X						2	X										THESE POSTS ARE NOT TO BE OPTIONED.		E-143M
8+212.0, LT	WEST	1	750	375	0.28						1						X																	THIS POST IS NOT TO BE OPTIONED.		E-136AM
	4	1	900	900	0.81																															E-136AM
8+567.0, RT	ONE WAY	1	900	300	0.27						1			X		X																				E-142M
8+758.0, LT		1	1200	1200	1.44						2						X																	THESE POSTS ARE NOT TO BE OPTIONED.		E-150M
												m	m 4.6	m 4.6	m	m 9.2	m 0.0/41.4		EA	kg	kg 30.0	kg		kg 194.1	kg	kg	kg								
TOTALS			m^2 10.54	m^2 6.44	EA	m^2						m 9.2			m 9.2/41.4					kg 30.0		EA 4		kg 194.1				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: FAIR HAVEN - RUTLAND

PROJECT NO.: NH 9727(I)S

DESIGN FILE NAME: /pave/96bl54/pbl54.dgn
IPARM FILE NAME: pbl54t06.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 8/98
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 81 OF 119