STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
U.S. ROUTE 4 8+862.0, LT	BR 10-W US4	1	150	200	0.03						1	X			X																					E-134M
9+150.0 ~~9+170.0,~~ LT	EXIT 4	1	1800	1500		2.70					2											2	X										18" DIA. FNDN .460MM POST 3" (2EA.)			E-131M
9+171.0, LT		1	450	450	0.20						1	X			X																					E-150M
9+316.0, LT	40 0000 5769	1	150	200	0.03						1	X			X																					E-138M
9+348.0, LT	EXIT 30 M.P.H.	1	1200	1500	1.80						2						X																THESE POSTS ARE NOT TO BE OPTIONED.			E-150M
9+415.0 ~~9+441.0,~~ LT	EXIT 4	1	2000	700	1.40						2																			2		527.5	~~W250X38.5~~		24" FNDN 600MM (3EA.)		E-131M
	30 Poultney Castleton Corners	1	6600	3150		20.79																													53	
9+450.0, RT		1	1200	1200	1.44						2											2	X													E-143M
9+656.0, LT	MILE 6	1	300	600	0.18						1		X			X																					E-139M
9+902.0, LT	EXIT 4	1	2700	2400		6.48					2																			2		118.8	W150X13.5		.460MM 18" DIA. FNDN 4" DIA. (2EA.)	54	
		1 1 1	600 600 600	600 600 600	0.36 0.36 0.36																															E-132M E-132M E-132M
	STATE POLICE	1 1 1	600 600 600	600 600 600	0.36 0.36 0.36																															E-132M E-132M E-132M
10+100.0 ~~10+146.0,~~ LT	EXIT 4	1	2000	700	1.40						3																			3		831.6	~~W250X38.5~~		W10X26 (24' DIA. FNDN 3 EA.)		E-131M
	30 Poultney Castleton Corners 1/2 MILE	1	6600	3750		24.75																													54	
TOTALS					m^2 ~~8.64~~ 8.01	m^2 ~~54.72~~ 54.72	EA	m^2				m 18.4			m 18.4/9.2							kg	EA 4				kg 172.9				EA 7	EA	kg 1477.9					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
FAIR HAVEN - RUTLAND	NH 9727(I)S

DESIGN FILE NAME: /pave/96bl54/pbl54.dgn
IPARM FILE NAME: pbl54t07.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 8/98
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 82 OF 119