STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	NEW & SALVAGED SIGNS: EA	SIGN DIMENSIONS: WIDTH (mm)	SIGN DIMENSIONS: HEIGHT (mm)	NEW & SALVAGED SIGNS: "A"	NEW & SALVAGED SIGNS: "B"	NEW & SALVAGED SIGNS: SALV SIGN	NEW & SALVAGED SIGNS: SALV TIS	EXIST POST: RETAIN	EXIST POST: SALVAGE	NEW SIGN POSTS: NO. OF POSTS	FLANGED CHANNEL kg/m: 1.7	FLANGED CHANNEL kg/m: 3.0	FLANGED CHANNEL kg/m: 4.5	SQUARE STEEL (mm) kg/m: 44 / 3.4	SQUARE STEEL (mm) kg/m: 50 / 3.9	SQUARE STEEL (mm) kg/m: 63 / 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m: 75 / 1.9	TUBULAR ALUMINUM Ø (mm) kg/m: 100 / 2.5	TUBULAR ALUMINUM Ø (mm) kg/m: 100 MOD / 2.5	TUBULAR STEEL Ø (mm): FOUNDATION	TUBULAR STEEL Ø (mm) kg/m: 75 / 11.3	TUBULAR STEEL Ø (mm) kg/m: 89 / 13.4	TUBULAR STEEL Ø (mm) kg/m: 100 / 16.1	TUBULAR STEEL Ø (mm) kg/m: 125 / 21.7	W-SHAPE STEEL FTG. SIZE: 600 mm	W-SHAPE STEEL FTG. SIZE: 750 mm	W-SHAPE STEEL: WEIGHT	W-SHAPE STEEL: POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
OPTION ITEMS																																					
U.S. ROUTE 4 12+489.0, RT	ONE WAY	1	900	300	0.27						1			X		X																				E-142M
12+727.0, LT		1	1200	1200	1.44						2						X																	THESE POSTS ARE NOT TO BE OPTIONED. SLIP BASE REQUIRED.		E-150M
12+858.0, LT	MILE 8	1	300	600	0.18						1		X			X																			E-139M
840.5 12+~~860.0~~, LT	EXIT 5	1	1800	1500		2.70					2												2	X									18" DIA. 3" DIA. FNDN 2 EA.		E-131M
12+861.0, LT		1	450	450	0.20						1	X			X																			E-150M
12+922.0, LT	5C 0000 8006	1	150	200	0.03						1	X			X																			E-138M
13+002.0, LT	EXIT 30 M.P.H.	1	1200	1500	1.80						2						X																	THESE POSTS ARE NOT TO BE OPTIONED.		E-150M
13+057.0, RT		1	1200	1200	1.44						2						X																	THESE POSTS ARE NOT TO BE OPTIONED. SLIP BASE REQUIRED.		E-143M
13+135.0, LT	EXIT 5	1	2000	700	1.40						2																				2		305.9	W200X26.6		FNDN 24" .600MM 2 EA.		E-131M
	TO Castleton	1	4950	2400		11.88																														55	
13+367.0, LT	EXIT 5	1	2700	2400		6.48					2																				2		230.4	W150X13.5		18" FNDN .460MM 5" DIA POST (2EA.)	55	
		1 1 1	600 600 600	600 600 600	0.36 0.36 0.36																																E-132M E-132M E-132M
		1	600	600	0.36																																E-132M
												m 9.2	m 4.6	m 4.6	m 9.2	m 9.2	m 0.0/27.6		EA	kg	kg	kg		kg 96.3	kg	kg	kg							
TOTALS					m^2 ~~8.20~~ 7.57	m^2 ~~21.06~~ 21.06	EA	m^2				m 18.4			m 18.4/27.6					kg			EA 2	kg 96.3				EA 4	EA	kg 536.3				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
FAIR HAVEN - RUTLAND	NH 9727(I)S

DESIGN FILE NAME: /pave/96bl54/pbl54.dgn
IPARM FILE NAME: pbl54t09.I
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 8/98
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 84 OF 119