STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
U.S. ROUTE 4 13+752.0, LT	EXIT 5	1	2000	700	1.40						2																	2		311.2	W200X26.6		24' FNDN .600MM (2EA.)		E-131M
	TO 4 Castleton 1/2 MILE	1	3900	3000		11.70																												56	
14+361.0, RT		1	1200	1200	1.44						2						X															THESE POSTS ARE NOT TO BE OPTIONED.		E-150M
	55 M.P.H.	1	600	600	0.36																														E-155M
14+361.0, LT		1	1200	1200	1.44						2			X			X																		E-150M
	55 M.P.H.	1	600	600	0.36																														E-155M
14+484.1, LT	MILE 9	1	300	600	0.18						1		X			X																			E-139M
14+531.0, RT		1	1200	1200	1.44						2						X															THESE POSTS ARE NOT TO BE OPTIONED.		E-143M
~~14+557.0~~ ~~14+552.~~0, LT	EXIT 5	1	2000	700	1.40						2																	2		447.6	W200X31.3		FNDN 24" DIA (2EA.)		E-131M
	TO 4 Castleton 1 MILE	1	3900	3000		11.70																												56	
16+093.4, LT	MILE 10	1	300	600	0.18						1		X			X																			E-139M
16+585.0, RT		1	1200	1200	1.44						2						X															THESE POSTS ARE NOT TO BE OPTIONED.		E-143M
											m	m 9.2	m 9.2	m	m 9.2	m 9.2/27.6	EA	kg	kg	kg		kg	kg	kg	kg									
TOTALS					m^2 ~~8.38~~ ~~9.64~~	m^2 ~~23.40~~ ~~23.40~~	EA	m^2				m 18.04			m 18.4/27.6					kg	EA	kg						EA 4	EA	kg 758.8					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
FAIR HAVEN - RUTLAND	NH 9727(I)S

DESIGN FILE NAME: /pave/96bl54/pbl54.dgn
IPARM FILE NAME: pbl54110.1
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 8/98
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 85 OF 119