STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
U.S. ROUTE 4 18+771.4, LT	ENTERING TOWN OF IRA	1	900	600	0.54						1			X		X																			66	
19+312.1, LT	MILE 1 2	1	300	600	0.18						1		X			X																				E-139M
19+902.0, LT	PARKING AREA 1 MILE	1	3750	1500		5.63					2											2		X									18" DIA. FNDN 3.5" DIA. POST (2EA.)	57	
20+817.0, RT		1	1200	1200	1.44						2						X																THESE POSTS ARE NOT TO BE OPTIONED.		E-143M
20+921.5, LT	MILE 1 3	1	300	600	0.18						1		X			X																				E-139M
20+990.0, LT	BR 13-W US4	1	150	200	0.03						1	X			X																				E-134M
21+196.5, LT	BR 14-W US4	1	150	200	0.03						1	X			X																				E-134M
21+489.0, LT	BRIDGES FREEZE BEFORE ROAD	1	1200	1200	1.44						2						X																THESE POSTS ARE NOT TO BE OPTIONED.		E-150M
22+530.8, LT	MILE 1 4	1	300	600	0.18						1		X			X																				E-139M
22+720.0, LT	Castleton 8 Fair Haven 12	1	2700	900		2.43					2										X													57	
097 23+~~091~~.0, LT	SPEED LIMIT 65	1	1200	1500	1.80						2											2	X												E-142M
	MINIMUM 40	1	1200	1200	1.44																												18" DIA. FNDN 3" DIA. POST (2)		E-142M
23+378.0, LT	WEST	1	750	375	0.28						1						X																THIS POST IS NOT TO BE OPTIONED.		E-136AM
	4	1	900	900	0.81																														E-136AM
												m 9.2	m 13.8	m 4.6	m 9.2	m 18.4	m 0.0/23.0		EA	kg	kg 30.0	kg		kg 132.9	kg 115.2	kg	kg							
TOTALS			m^2 8.35	m^2 8.06	EA	m^2						m 27.6			m 27.6/23.0					kg 30.0			EA 4	kg 248.1				EA	EA	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: FAIR HAVEN - RUTLAND
PROJECT NO.: NH 9727(I)S

DESIGN FILE NAME: /pave/96bl54/pbl54.dgn
IPARM FILE NAME: pbl54112.1
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 8/98
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 87 OF 119