STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																										
U.S. ROUTE 4 ~~470.0~~ 24+~~425.0~~, LT	EXIT 6	1	2000	700	1.40						4																	4		889.4	W250X32.7		600MM FNDN (4EA.)		E-131M
	4 TO 91 TO 3 Proctor West Rutland	1	7350	4200		30.87																												58	
	NEXT EXIT 7 MILES	1	4050	600		2.43																													E-131M
~~870.0~~ 24+~~825.0~~, LT	EXIT 6	1	2700	2400		6.48					2																	2		147.2	W150X13.5		18" DIA. FNDN 4" DIA. (2EA.)	58	
		1 1 1	600 600 600	600 600 600	0.36 0.36 0.36																														E-132M E-132M E-132M
		1	600	600	0.36																														E-132M
~~227.0~~ 25+~~180.0~~, LT	EXIT 6	1	2000	700	1.40						4																		4	1459.6	W310X44.5		30" 750MM FNDN 4 EA		E-131M
	4 TO 91 TO 3 Proctor West Rutland 1/2 MILE	1	6450	5100		32.90																												59	
25+749.5, LT	MILE 1 6	1	300	600	0.18						1		X			X																			E-139M
25+924.0, LT	EXIT 6	1	2000	700	1.40						4																		4	1521.9	W310X44.5		30" 750MM FNDN 4 EA		E-131M
	4 TO 91 TO 3 Proctor West Rutland 1 MILE	1	6450	5100		32.90																												59	
26+384.0, LT	ENTERING TOWN OF W. RUTLAND	1	900	600	0.54						1			X		X																		66	
26+538.0, RT		1	1200	1200	1.44						2						X																THESE POSTS ARE NOT TO BE OPTIONED.		E-143M
27+358.8, LT	MILE 1 7	1	300	600	0.18						1		X			X																			E-139M
											m	m 9.2	m 4.6		m	m 13.8	m 0.0/ 9.2		EA	kg	kg	kg		kg	kg	kg	kg								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TOTALS	m^2 ~~7.98~~ 7.35	m^2 ~~105.6~~ 105.6	EA	m^2		m 13.8	m 13.8/9.2	kg	EA	kg	EA 6	EA 8	kg 4018.1

PROJECT: FAIR HAVEN - RUTLAND	PROJECT NO.: NH 9727(I)S
DESIGN FILE NAME: /pave/96bl54/pbl54.dgn	
IPARM FILE NAME: pbl54tl4.1	PLOT DATE: 8/98
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: C.A.K.
	SHEET: 89 OF 119