STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
U.S. ROUTE 4 28+058.0, RT		1	1200	1200	1.44						2						X																	THESE POSTS ARE NOT TO BE OPTIONED.		E-143M
28+365.5, LT	BR 19-W US4	1	150	200	0.03						1	X			X																				E-134M
28+631.0, RT		1	1200	1200	1.44						2						X																	THESE POSTS ARE NOT TO BE OPTIONED.		E-143M
28+812.0, LT	BR 20-W US4	1	150	200	0.03						1	X			X																				E-143M
28+840.0, LT	Otter Creek	1	1350	1050	1.42						2						X																	THESE POSTS ARE NOT TO BE OPTIONED.	69	
28+968.2, LT	MILE 1 8	1	300	600	0.18						1		X			X																			E-139M
28+993.0, LT	BRIDGES FREEZE BEFORE ROAD	1	1200	1200	1.44						2			X			X																			E-150M
29+376.0, LT	West Rutland 4 Fair Haven 16	1	3000	900		2.70					2												2	X										18" DIA. FNDN .460MM 3" DIA. POST (2EA.)	58	
570 29+~~468.~~0, LT	SPEED LIMIT 65	1	1200	1500	1.80						2												2	X										18" DIA. FNDN .460MM 3" DIA. POST (2EA.)		E-142M
	MINIMUM 40	1	1200	1200	1.44																															E-142M
29+530.0, RT		1	1200	1200	1.44						2						X																	THESE POSTS ARE NOT TO BE OPTIONED.		E-143M
900 29+~~845.~~0, RT	R R	1	800	800	0.64						1			X		X																				E-190M
900 29+~~845.~~0, LT	R R	1	800	800	0.64						1			X		X																				E-190M
											m 9.2	m 4.6	m 18.4	m 9.2	m 13.8	m 9.2/36.8		EA	kg	kg	kg		kg 226.2	kg	kg	kg								
TOTALS					m^2 ~~11.94~~ 10.05	m^2 ~~2.70~~ 2.70	EA	m^2			m 32.2			m 32.2/36.8					kg	EA 4			kg 226.2				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: FAIR HAVEN - RUTLAND

PROJECT NO.: NH 9727(I)S

DESIGN FILE NAME: /pave/96bl54/pbl54.dgn
IPARM FILE NAME: pbl54tl5.1
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.

PLOT DATE: 8/98
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 90 OF 119