STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INTERCHANGE 6 RAMP "D" D0+146.0, RT	WEST RUTLAND 1 / BOARDMAN HILL RD — WRONG WAY	1	1800	250	0.45						2			X			X																	BACK-TO-BACK	64	
		1	1800	250	0.45																														64	
		1	1050	750	0.79																															E-142M
	SERVICES →	1	1350	185	0.25																															E-133M
D0+146.0, LT	WRONG WAY	1	1050	750	0.79						1			X		X																	MOUNT SIGN IN DIRECTION OF OPPOSING TRAFFIC.		E-142M
		1	600	600	0.36																													MOUNT SIGN IN DIRECTION OF OPPOSING TRAFFIC.		E-143M
D0+195.0, LT		1	450	450	0.20						1	X			X																					
D0+201.0, LT	TO	1	750	375	0.28						1						X																X	THIS POST IS NOT TO BE OPTIONED.		E-136BM
	VERMONT 4A	1	900	900	0.81																															E-136BM
		1	525	375	0.20																															E-136BM
INTERCHANGE 6 RAMP "E" E0+017.0, RT		1	450	450	0.20						1	X			X																					E-150M
E0+049.0, RT		1	1200	1200	1.44						2						X																	THESE POSTS ARE NOT TO BE OPTIONED.		E-143M
E0+067.0, RT	STOP — DO NOT ENTER	1	1200	1200	1.44						2						X																	THESE POSTS ARE NOT TO BE OPTIONED. BACK-TO-BACK		E-143M
		1	1200	1200	1.44																															E-143M
	ONE WAY — ONE WAY	1	900	300	0.27																													BACK-TO-BACK		E-142M
		1	900	300	0.27																															E-142M
											m	m	m	m	m	m	EA	kg	kg	kg		kg	kg	kg	kg									
											9.2		13.8	9.2	4.6	9.2/23.0																		
TOTALS			m^2 9.64	m^2	EA	m^2					m 23.0			m 23.0/23.0				kg	EA	kg					EA	EA	kg							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: FAIR HAVEN - RUTLAND	PROJECT NO.: NH 9727(I)S
DESIGN FILE NAME: /pave/96bl54/pbl54.dgn	
IPARM FILE NAME: pbl54t24.I	PLOT DATE: 8/98
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: C.A.K.
	SHEET: 99 OF 119