STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric (VAOT)

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
INTERCHANGE 6 RAMP "E" E0+067.0, LT	STOP DO NOT ENTER	1 1	1200 1200	1200 1200	1.44 1.44						2						X																THESE POSTS ARE NOT TO BE OPTIONED. BACK-TO-BACK		E-143M E-143M
	← ONE WAY ONE WAY →	1 1	900 900	300 300	0.27 0.27																												BACK-TO-BACK		E-142M E-142M
INTERCHANGE 6 RAMP "F" F0+000.0, LT	6F 000 D109	1	150	200	0.03						1	X			X																				E-138M
F0+042.0, RT	STOP DO NOT ENTER	1 1	1200 1200	1200 1200	1.44 1.44						2						X																THESE POSTS ARE NOT TO BE OPTIONED. BACK-TO-BACK		E-143M E-143M
	← ONE WAY ONE WAY →	1 1	900 900	300 300	0.27 0.27																												BACK-TO-BACK		E-142M E-142M
F0+042.0, LT	STOP DO NOT ENTER	1 1	1200 1200	1200 1200	1.44 1.44						2						X																THESE POSTS ARE NOT TO BE OPTIONED. BACK-TO-BACK		E-143M E-143M
	← ONE WAY ONE WAY →	1 1	900 900	300 300	0.27 0.27																												BACK-TO-BACK		E-142M E-142M

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

Subtotals: Flanged channel m 4.6 / m / m; Square steel m 4.6 / m / m 0.0/27.6; Sleeve EA; Tubular aluminum kg / kg / kg; Tubular steel kg / kg / kg / kg

TOTALS	"A"	"B"	SALV SIGN	SALV TIS	FLANGED CHANNEL	SQUARE STEEL	TUBULAR ALUMINUM	FOUNDATION	TUBULAR STEEL	FTG. 600	FTG. 750	WEIGHT
units	m^2	m^2	EA	m^2	m	m	kg	EA	kg	EA	EA	kg
total	10.29				4.6	4.6/27.6						

PROJECT: FAIR HAVEN - RUTLAND
PROJECT NO.: NH 9727(1)S
DESIGN FILE NAME: /pave/96b154/pb154.dgn
IPARM FILE NAME: pb154t25.1
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 8/98
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 100 OF 119