STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INTERCHANGE 1 SIDELINE 100+016.1, LT	WEST EAST	1	600	300	0.18						2						X																X	THESE POSTS ARE NOT TO BE OPTIONED.		E-136AM
		1	600	300	0.18																														E-136AM
	4 4	1	600	600	0.36																														E-136AM
		1	600	600	0.36																														E-136AM
	← →	1	525	375	0.20																														E-136AM
		1	525	375	0.20																														E-136AM
100+073.6, RT	EAST	1	600	300	0.18						1			X			X																		E-136BM
	VERMONT 4A	1	600	600	0.36																														E-136BM
100+098.6, LT	← WHITEHALL NY 5	1	1800	250	0.45						2			X		X																			60	
	RUTLAND 18 →	1	1800	250	0.45																														60	
100+128.6, LT	JCT	1	525	375	0.20						1			X			X																		E-136AM
	4	1	600	600	0.36																														E-136AM
INTERCHANGE 2 SIDELINE 200+170.0, RT	JCT	1	525	375	0.20						1			X			X																		E-136AM
	4	1	600	600	0.36																														E-136AM
200+230.0, RT	↑ WHITEHALL NY 7	1	1800	250	0.45						2			X		X																			67	
	CASTLETON 7 →	1	1800	250	0.45																														67	
	RUTLAND 16 →	1	1800	250	0.45																														68	
											m	m	m 32.2	m	m 18.4	m 13.8/9.2		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS			m^2 5.39	m^2	EA	m^2					m 32.2			m 32.2/9.2					kg	EA	kg						EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
FAIR HAVEN - RUTLAND	NH 9727(I)S

DESIGN FILE NAME: /pave/96bl54/pbl54.dgn
IPARM FILE NAME: pbl54t26.I
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 8/98
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 101 OF 119