STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INTERCHANGE 2 SIDELINE 200+514.0, LT	EAST SOUTH	1	600	300	0.18						2						X															X	THESE POSTS ARE NOT TO BE OPTIONED.		E-136AM
		1	600	300	0.18																														E-136BM
	4 VERMONT 22A	1	600	600	0.36																														E-136AM
		1	600	600	0.36																														E-136BM
		1	525	375	0.20																														E-136AM
		1	525	375	0.20																														E-136BM
200+520.0, RT	WEST	1	600	300	0.18						1			X			X																		E-136AM
	4	1	600	600	0.36																														E-136AM
		1	525	375	0.20																														E-136AM
200+561.0, LT	EAST SOUTH WEST	1	600	300	0.18						2												2	X							X				E-136AM
		1	600	300	0.18																														E-136BM
		1	600	300	0.18																														E-136AM
	4 VERMONT 22A 4	1	600	600	0.36																														E-136AM
		1	600	600	0.36																														E-136BM
		1	600	600	0.36																														E-136AM
		1	525	375	0.20																														E-136AM
		1	525	375	0.20																														E-136BM
		1	525	375	0.20																														E-136AM
200+566.0, RT	NORTH	1	600	300	0.18						1			X			X																		E-136BM
	VERMONT 22A	1	600	600	0.36																														E-136BM
												m	m	m 9.2	m	m	m 9.2/9.2		EA	kg	kg	kg		kg 84.8	kg	kg	kg								
TOTALS			m² 4.98	m²	EA	m²						m 9.2			m 9.2/9.2						kg	EA 2	kg 84.8				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
FAIR HAVEN - RUTLAND	NH 9727(I)S

DESIGN FILE NAME: /pave/96bl54/pbl54.dgn
IPARM FILE NAME: pbl54t28.I
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 8/98
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 103 OF 119