STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
INTERCHANGE 2 SIDELINE 200+61 0. 0, LT	WHITEHALL NY 7 →	1	1 800	250	0. 45																														67	
	↑ CASTLETON 7	1	1 800	250	0. 45						2			X			X																		67	
	↑ RUTLAND 16	1	1 800	250	0. 45																														68	
200+626. 0, LT	↑ VERGENNES 30	1	1 800	250	0. 45						2		X			X																		67	
200+670. 0, RT	JCT	1	525	375	0. 20						1			X			X																			E-1 36AM
	4	1	600	600	0. 36																															E-1 36AM
INTERCHANGE 3 SIDELINE 300+020. 0, RT	JCT	1	525	375	0. 20						1			X			X																			E-1 36AM
	4	1	600	600	0. 36																															E-1 36AM
300+080. 0, RT	↑ WEST CASTLETON 5	1	1 800	250	0. 45																														60	
	CASTLETON 6 →	1	1 800	250	0. 45						2			X			X																		60	
	RUTLAND 17 →	1	1 800	250	0. 45																														60	
300+080. 0, LT	↑ FAIR HAVEN 1	1	1 800	250	0. 45						2		X			X																		61	
300+1 23. 0, RT	EAST	1	600	300	0. 18						1			X			X																			E-1 36AM
	4	1	600	600	0. 36																															E-1 36AM
	→	1	525	375	0. 20																															E-1 36AM
												m	m 18.4	m 32.2	m	m 18.4	m 32.2		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS			m^2 5.46	m^2	EA	m^2						m 50.6			m 50.6					kg	EA	kg		EA	EA	kg								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: FAIR HAVEN - RUTLAND

PROJECT NO.: NH 9727(I)S

DESIGN FILE NAME: /pave/96bl54/pbl54.dgn
IPARM FILE NAME: pbl54t29.1
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.

PLOT DATE: 8/98
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 104 OF 119