STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
INTERCHANGE 5 SIDE LINE 500+003.0, RT	JCT	1	525	375	0.20						1			X			X																			E-136AM
	4	1	600	600	0.36																															E-136AM
500+110.0, RT	FAIR HAVEN 5	1	1800	250	0.45						2			X		X																			63	
	RUTLAND 11 →	1	1800	250	0.45																															65	
500+150.0, RT	WEST EAST	1	600	300	0.18						2						X																	X	THESE POSTS ARE NOT TO BE OPTIONED.		E-136AM
		1	600	300	0.18																															E-136AM
	4 4	1	600	600	0.36																															E-136AM
		1	600	600	0.36																															E-136AM
	↑ ↗	1	525	375	0.20																															E-136AM
		1	525	375	0.20																															E-136AM
500+190.0, LT	EAST JCT	1	600	300	0.18						2						X																	X	THESE POSTS ARE NOT TO BE OPTIONED.		E-136AM
		1	525	375	0.20																															E-136BM
	4 VERMONT 4A	1	600	600	0.36																															E-136AM
		1	600	600	0.36																															E-136BM
	←	1	525	375	0.20																															E-136AM
500+245.0, RT	WEST	1	600	300	0.18						1			X			X																			E-136AM
	4	1	600	600	0.36																															E-136AM
	↱	1	525	375	0.20																															E-136AM
TOTALS		m² 4.98		m²	EA	m²						m 18.4			m 18.4/18.4					kg	EA	kg							EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: FAIR HAVEN - RUTLAND	PROJECT NO.: NH 9727(I)S
DESIGN FILE NAME: /pave/96bl54/pbl54.dgn	
IPARM FILE NAME: pbl54t34.I	PLOT DATE: 8/98
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: C.A.K.
	SHEET: 109 OF 119