QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

FULL E&C	EROSION CONTROL	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		22	22	EA	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50	-
		190	190	LF	DURABLE CROSSWALK MARKING W/ DIAG. LINES (THERMOPLASTIC) (MOD. - BLOCK TYPE)	646.51	9
		3800	3800	LF	TEMPORARY 4'' WHITE LINE (PAINT)	646.60	30
		1300	1300	LF	TEMPORARY 4'' YELLOW LINE (PAINT)	646.61	15
		150	150	LF	TEMPORARY 24" STOP BAR (PAINT)	646.66	6
		44	44	EA	TEMPORARY LETTER OR SYMBOL (PAINT)	646.70	-
		380	380	LF	TEMP. CROSSWALK MARKING W/ DIAG. LINES (PAINT) (MOD. - BLOCK TYPE)	646.71	9
	5		5	LB	SEED	651.15	
	30		30	LB	FERTILIZER	651.18	
	.1		.1	TON	AGRICULTURAL LIMESTONE	651.20	
	.1		.1	TON	HAY MULCH	651.25	
	20		20	CY	TOPSOIL	651.35	
		27.42	27.42	SF	TRAFFIC SIGNS (TYPE A)	675.20	-
					** BEGIN OPTION POSTS **		
		83	83	LF	FLANGED CHANNEL SIGN POSTS	675.301	-
		83	83	LF	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341	-
					** END OPTION POSTS **		
		13	13	EA	REMOVING SIGNS	675.50	-
		19	19	EA	ERECTING SALVAGED SIGNS	675.60	-
		1	1	EA	TRAFFIC CONTROL SIGNAL SYSTEM - INTERSECTION	678.15	-
		1720	1720	LF	VEHICLE LOOP DETECTOR	678.22	-
		400	400	LF	WIRED CONDUIT, (1-1/2'') (PVC)	678.23	7
		375	375	LF	WIRED CONDUIT, (2'') (PVC)	678.23	22
		3	3	EA	PULL BOX - STANDARD	678.25	-
		200	200	LF	ELECTRICAL CONDUIT SLEEVE (6")	678.30	7

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: ESSEX
PROJECT NUMBER: STPG SGNL (17)

FILE NAME: /traf/96bl82/tbl82nul.dgn/dbl82qt2.l
PROJECT LEADER: B. NYQUIST
DESIGNED BY: B. MCAVOY
PLOT DATE: 16-NOV-2006
DRAWN BY: B. MCAVOY
CHECKED BY: B. NYQUIST
SHEET 4 OF 29