

QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES										DETAILED SUMMARY OF QUANTITIES			DETAILED SUMMARY OF QUANTITIES			
				BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND	QUANTITIES	UNIT	ITEMS	QUANTITIES	UNIT	ITEMS
				80		80	m	HEAVY DUTY STEEL BEAM GUARDRAIL	621.21	-						
				24		24	EA	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.63	-						
				23	30	53	EA	MODIFIED ECCENTRIC LOADER TERMINAL	621.94	-						
				7	4	11	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-						
				850	1295	2145	m	REMOVAL AND DISP. OF GUARDRAIL	621.80	26						
				5	28	33	EA	REMOVAL AND DISP. OF GUIDE POSTS	621.81	2						
					840	840	HR	UNIFORMED TRAFFIC OFFICERS (N.A.B.I.)	630.10	EST.						
					1230	1230	HR	FLAGGERS (N.A.B.I.)	630.15	EST.						
					1	1	LS	FIELD OFFICE ENGINEER	631.10							
					1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16							
					1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17							
					1	1	LS	FIELD OFFICE - TELEPHONE (N. A. B. I.)	631.25							
					1	1	LS	MOBILIZATION	635.10							
				25550	25550	25550	m	DURABLE 100 mm WHITE LINE	646.40	285						
				22500	22500	22500	m	DURABLE 100 mm YELLOW LINE	646.41	241						
				7	7	7	m	DURABLE 600 mm STOP BAR	646.46	1						
				16	16	16	EA	DURABLE LETTER OR SYMBOL	646.50	-						
				19	19	19	m	DURABLE CROSSWALK MARKING W/ DIAGONAL LINES	646.51	1						
				25550	25550	25550	m	TEMPORARY 100 mm WHITE LINE	646.60	285						
				22500	22500	22500	m	TEMPORARY 100 mm YELLOW LINE	646.61	241						
				7	7	7	m	TEMPORARY 600 mm STOP BAR	646.66	1						
				16	16	16	EA	TEMPORARY LETTER OR SYMBOL	646.70	-						
				19	19	19	m	TEMPORARY CROSSWALK MARKING W/ DIAGONAL LINES	646.71	1						
				1000	1000	1000	EA	LINE STRIPING TARGETS	646.76	17						
				15	15	15	kg	SEED	651.15	EST.						
				115	115	115	kg	FERTILIZER	651.18	EST.						
				1	1	1	†	AGRICULTURAL LIMESTONE	651.20	EST.						
				1	1	1	†	HAY MULCH	651.25	EST.						
				20	20	20	m3	TOPSOIL	651.35	EST.						
				30	30	30	m2	TRAFFIC SIGNS, TYPE A	675.20	135						
								*** BEGIN OPTION ITEMS ***								
				995	995	995	kg	FLANGED CHANNEL SIGN POSTS	675.30	13						
				995	995	995	kg	SQUARE TUBE STEEL POSTS AND ANCHORS	675.34	13						
								*** END OPTION ITEMS ***								
				80	80	80	EA	REMOVING SIGNS	675.50	-						
				4	4	4	EA	ERECTING SALVAGED SIGNS	675.60	-						

PROJECT 1 STAMFORD-READSBORO	PROJECT NO. 1 STP 971111S
DESIGN FILE NAME: /pav/96c020/pc020.dgn	
IPARM FILE NAME: pc020982.d	PLOT DATE: 24-MAR-1997
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: JAW	DRAWN BY: SMC
	SHEET: 4 OF 28