STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET

Metric

| KILOMETER MARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | WIDTH (mm) | HEIGHT (mm) | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | SALVAGE | NO. OF POSTS | FLANGED CHANNEL kg/m 1.7 | 3.0 | 4.5 | SQUARE STEEL (mm) 44 kg/m 3.4 | 50 kg/m 3.9 | 63 kg/m 5.0 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9 | 100 kg/m 2.5 | 100 MOD. 2.5 | TUBULAR STEEL Ø (mm) FOUND-ATION | 75 kg/m 11.3 | 89 kg/m 13.4 | 100 kg/m 16.1 | 125 kg/m 21.7 | W-SHAPE STEEL FTG. SIZE 600 mm | 750 mm | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL DETAIL ON SHEET NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | OPTION ITEMS | | | | | | | | | | | | | | | | | | | | | | | | |
| 6+022.3 ~~6+037.000~~ RT | SOUTH | 1 | | | | | 1 | | | | 1 | | | X 4.27 | | | | | | | | | | | | | | | | | | | ERECT SALVAGED SIGN 6+022.300 RT | | |
| 6+022.3 ~~6+037.000~~ RT | VERMONT 12 | 1 | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | ERECT SALVAGED SIGN 6+022.300 RT | | |
| 6+022.3 ~~6+037.000~~ RT | → | 1 | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | ERECT SALVAGED SIGN 6+022.300 RT | | |
| 6+032.4 ~~6+051.500~~ LT | STOP 0120 404 0176 | 1 | | | | | 2 + | | | | 1 | | | X 3.66 | | | | | | | | | | | | | | | | | | | ERECT SALVAGED SIGN 6+032.400 LT | | |
| 6+032.3 ~~6+051.500~~ LT | N. MAIN ST | 1 | | | | | 1 | | | | 1 | | | X 3.81 | | | | | | | | | | | | | | | | | | | ERECT SALVAGED SIGN 6+032.350 LT | | |
| 3+190.000 LT | SPEED LIMIT 25 REMOVAL | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | REMOVE SIGN | | |
| 3+080.000 LT | ⚠ | 1 | 750 | 750 | 0.563 | | | | | | 1 | | | X 4.45 | | | | | | | | | | | | | | | | | | | W11-2 | | E-152M |
| 3+080.000 LT | AHEAD | 1 | 600 | 200 | 0.120 | | | | | | | | | | | | | | | | | | | | | | | | | | | | S4-3 | | E-153M |
| 6+007 ~~6+030.600~~ RT | NORTH | 1 | | | | | 1 | | | | 1 | | | X 4.27 | | | | | | | | | | | | | | | | | | | ERECT SALVAGED SIGN 6+007.000 RT | | |
| 6+007 ~~6+030.600~~ RT | VERMONT 12 | 1 | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | ERECT SALVAGED SIGN 6+007.000 RT | | |
| 6+007 ~~6+030.600~~ RT | ← | 1 | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | ERECT SALVAGED SIGN 6+007.000 RT | | |
| 6+030.2 ~~6+050.000~~ LT | NORTH | 1 | | | | | 1 | | | | 1 | | | X 4.27 | | | | | | | | | | | | | | | | | | | ERECT SALVAGED SIGN 6+030.200 LT | | |
| 6+030.2 ~~6+050.000~~ LT | VERMONT 12 | 1 | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | ERECT SALVAGED SIGN 6+030.200 LT | | |
| 6+030.2 ~~6+050.000~~ LT | → | 1 | | | | | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | ERECT SALVAGED SIGN 6+030.200 LT | | |
| 2+940, RT ~~SEE LAYOUT SHEET~~ | ↱ | | 750 | 750 | 0.563 | | | | | | 1 | | | X 4.57 | | | | | | | | | | | | | | | | | | | COLOR SHALL BE BLACK ON REFLECTORIZED YELLOW W1-3R | | E-101M |
| 2+940, RT ~~SEE LAYOUT SHEET~~ | 20 MPH | | 450 | 450 | 0.203 | | | | | | ~~1~~ | | | ~~X~~ | | | | | | | | | | | | | | | | | | | W13-1 | | E-155M |
| 3+209.000 RT | SPEED LIMIT 25 | | 600 | 750 | 0.450 | | | | | | 1 | | | X 3.96 | | | | | | | | | | | | | | | | | | | R2-1 | | E-142M |
| | | | | | | | | | | | | m | m | m 39.5 | m | m | m | | EA | kg | kg | kg | | kg | kg | kg | kg | | | | | | | | |
| **TOTALS** | | | | | m² 1.90 | m² | EA. ~~11~~ 12 | m² | | | | m 39.5 | | | m | | | | | kg | | | EA. | kg | | | | EA. | EA. | kg | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BETHEL
PROJECT NUMBER: BRF 0241 (33)-C1

FILE NAME: 96J250/structures/a96j250tss-c1.dgn PLOT DATE: 09-JUL-2003
PROJECT LEADER: C. P. WILLIAMS DRAWN BY: T. G. ANDERSON
DESIGNED BY: K. M. HIGGINS CHECKED BY: K. M. HIGGINS
TRAFFIC SIGN SUMMARY SHEET 1 SHEET 14 OF 47