STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

APPROXIMATE SUMMARY OF QUANTITIES

	R.O.W.		NON GOV'T PARTICIPATING	EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				-	-	650	650	m^3	COMMON EXCAVATION	203.15	42
				-	-	550	550	m^3	EXCAVATION OF SURFACES AND PAVEMENTS	203.28	24.0
				-	-	1	1	m^3	EARTH BORROW (NOT A BID ITEM)	203.30	-
				-	-	40	40	m	SHOULDER BERM REMOVAL	203.99	3
				-	-	1	1	m^3	TRENCH EXCAVATION OF EARTH (NOT A BID ITEM)	204.20	-
				-	-	29,000	29,000	m^2	COLD PLANING - BITUMINOUS PAVEMENT	210.10	1114
				-	-	1800	1800	t	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	EST.
				-	-	670	670	m^3	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	30
				-	-	2650	2650	t	AGGREGATE SHOULDERS (MOD.)	402.12	100
				-	-	58,000	58,000	kg	EMULSIFIED ASPHALT	404.65	2372
				-	-	1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (NOT A BID ITEM)	406.50	-
				-	-	30,500	30,500	t	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	490.30	1200
				-	40	-	40	m	BRIDGE EXPANSION JOINT	516.10	1.3
				-	10	-	10	m	REMOVAL OF EXISTING RAILING	525.10	1.6
				-	15	-	15	m	BRIDGE RAIL-HD STEEL BEAM/CURB MOUNTED (MOD. 2)	525.40	3.6
				-	-	2	2	EA	CHANGING ELEVATION OF DI'S, CB'S OR MH'S	604.40	-
				-	-	8	8	EA	REHABING DI'S, CB'S OR MH'S, CLASS I	604.412	-
				-	-	125	125	HR	POWER GRADER RENTAL	608.15	EST.
				-	-	425	425	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
				-	-	75	75	HR	POWER BROOM RENTAL	608.30	EST.
				-	-	75	75	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
				-	-	850	850	HR	TRUCK RENTAL	608.37	EST.
				-	-	2	2	t	DUST AND ICE CONTROL CALCIUM CHLORIDE	609.15	EST.
				-	-	200	200	m^3	STONE FILL, TYPE I	613.10	EST.
				-	-	500	500	m	TREATED TIMBER CURB	616.35	20
				-	-	50	50	t	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	EST.
				-	-	1180	1180	t	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS (MOD.)	616.47	56
				-	-	2	2	EA	RELOCATING MAIL BOX, SINGLE SUPPORT	617.10	-
				-	-	1	1	EA	RELOCATE MAIL BOX, MULTIPLE SUPPORT	617.12	-
				-	-	60	60	EA	YIELDING MARKER POSTS	619.17	-
				-	-	5150	5150	m	STEEL BEAM GUARDRAIL	621.20	175.8
				-	-	1450	1450	m	STEEL BEAM GUARDRAIL W/2.4 m POSTS (MOD.)	621.20	65.6
				-	-	20	20	m	HEAVY DUTY STEEL BEAM GUARDRAIL	621.21	4.8
				-	-	3	3	EA	MANUFACTURED TERMINAL SECTION	621.505	-
				-	-	62	62	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	-
				-	-	4	4	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
				-	-	6600	6600	m	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	278.8
				-	-	20	20	EA	REMOVAL AND DISPOSAL OF GUIDEPOSTS	621.81	-
				-	-	1000	1000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
20,058	m^2	U.S. ROUTE 4
5682	m^2	SIDE ROADS
2146	m^2	DRIVES & PARKING AREAS
1114	m^2	ROUNDING
29,000	m^2	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-34)
7740	t	LEVELING COURSE (TYPE IV S)
20,664	t	WEARING COURSE (TYPE III S)
579	t	SIDE ROADS
317	t	DRIVES & PARKING AREAS
1200	t	ROUNDING
30,500	t	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS		PAVEMENT WIDTHS			EQUATIONS				REMARKS
FROM	TO				+	-			
TOTALS									/pave/97bl60/pbl60.dgn pbl60qsl.i

FINAL QUANTITIES ARE ARCHIVED WITH THE FIELD BOOKS

ARCHIVED IN DPR

PROJECT NAME RUTLAND - KILLINGTON
PROJECT NUMBER NH 9809(11)S

USER=$NTUSER$