STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																								
RUTLAND: 0+358.0, LT (O/H SIGN)		1 1 1	900 900 900	1200 1200 1200	1.08 1.08 1.08																													SIGNS TO BE CENTERED OVER RESPECTIVE LANES.	80 79	- - E-144M
							1																											SALVAGED SIGN TO BE MOUNTED ON CANTILEVER SUPPORT.	-	-
0+411.0, RT							1				1			X																				SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
							1																											SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
0+505.0, RT		1	750	750	0.56						1			X																						E-152M
0+511.0, LT		1	600	600	0.36						1			X																						E-143M
		1	600	300	0.18																															E-140M
0+578.0, LT		1	900	900	0.81						2			X																						E-152M
0+614.0, LT		1	600	600	0.36						1			X																						E-143M
		1	600	300	0.18																															E-140M
0+643.7, LT		1	150	200	0.03						1	X																								E-138M
												m 4.6	m	m 27.6	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg									
	TOTALS				m² 5.72	m²	EA 3	m²				m 32.2			m					kg			EA	kg				EA	EA	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

ARCHIVED IN DPR

PROJECT: RUTLAND - KILLINGTON	PROJECT NO.: NH 9809(1)S
DESIGN FILE NAME: /pave/97b160/pb160.dgn	
IPARM FILE NAME: pb160t02.i	PLOT DATE: 11/99
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: I.P.K.	DRAWN BY: C.A.K.
	SHEET: 47 OF 83