STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
RUTLAND: 1+243.0, LT	SPEED LIMIT 45	1	600	750	0.45						1			X																					E-142M
1+243.0, RT	SPEED LIMIT 45	1	600	750	0.45						1			X																					E-142M
1+310.0, RT	SLOWER TRAFFIC KEEP RIGHT	1	600	750	0.45						1			X																					E-141M
1+321.0, LT	POST RD						1				1		X																					SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
	← RUT. TOWN / RUT. TOWN →						1 1																											SALVAGED SIGN TO BE MOUNTED ON NEW POST. BACK-TO-BACK	- -	- -
	← ELEM. SCHOOL / ELEM. SCHOOL →						1 1																											SALVAGED SIGN TO BE MOUNTED ON NEW POST. BACK-TO-BACK	- -	- -
	← NORTHWOOD POOL / NORTHWOOD POOL →						1 1																											SALVAGED SIGN TO BE MOUNTED ON NEW POST. BACK-TO-BACK	- -	- -
1+321.0, LT	STOP 0040 1120 0082	1 1	750 150	750 200	0.56 0.03		1				1			X																				BACK-TO-BACK		E-143M E-138M
1+336.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X																					E-141M
	NO THRU TRUCKS	1	600	600	0.36																														79	-
1+539.0, LT		1	750	750	0.56						1			X																						80	-
1+550.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X																					E-141M
1+562.0, RT	BELLEVIEW LN						1				1		X																					SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
1+562.0, RT	STOP 0040 1120 0097	1 1	750 150	750 200	0.56 0.03						1			X																					BACK-TO-BACK		E-143M E-138M
	TOTALS				m^2 4.35	m^2	EA 8	m^2				m 46.0	m 9.2	m 36.8	m	m	m		EA	kg	kg	kg	EA	kg	kg	kg	kg	EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

ARCHIVED IN DPR

PROJECT: RUTLAND - KILLINGTON
PROJECT NO.: NH 9809(1)S
DESIGN FILE NAME: /pave/97b160/pb160.dgn
IPARM FILE NAME: pb160t04.i
SURVEYED BY: N/A
SQUAD LEADER: I.P.K.
PLOT DATE: 11/99
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 49 OF 83