STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
MENDON: 0+716.0, LT	UNSAFE TO PASS	1	900	900	0.81						2			X																					E-150M
0+756.0, RT		1	300	900	0.27						1		X																					79	-
0+874.0, RT		1	750	750	0.56						1			X																					E-151M
0+965.0, RT	0040 1110 0060	1	150	200	0.03						1	X																							E-138M
1+101.6, RT	TRUCK LANE ENDS	1	600	750	0.45						1			X																					E-141M
1+115.0, LT	UNSAFE TO PASS	1	900	900	0.81						2			X																					E-150M
1+269.0, LT	SPEED LIMIT 45	1	600	750	0.45						1			X																					E-142M
	0040 1110 0080	1	150	200	0.03																														E-138M
1+269.0, RT	SPEED LIMIT 45	1	600	750	0.45						1			X																					E-142M
												m 4.6	m 4.6	m 36.8	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS					m² 3.86	m²	EA	m²				m 46.0			m					kg			EA	kg				EA	EA	kg					

ARCHIVED IN DPR

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: RUTLAND - KILLINGTON
PROJECT NO.: NH 9809(1)S
DESIGN FILE NAME: /pave/97b160/pb160.dgn
IPARM FILE NAME: pb160t07.i
SURVEYED BY: N/A
SQUAD LEADER: I.P.K.
PLOT DATE: 11/99
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 52 OF 83